

WELL PLUGGING RECORD

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Pawnee County, Sec. 36 Twp. 20 Rge. 16 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE SE NE

Lease Owner Brunson Production & Exploration, Inc.

Lease Name Schmidt #1 Well No.

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 12-1-58 19

Plugging completed 12-4-58 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot

Producing formation Depth to top Bottom Total Depth of Well 3837 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE   | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8-5/8" | 1010'  | none       |
|           |         |      |    | 5-1/2" | 3837'  | 3175'      |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked the hole to 3837' and found it open.  
Filled w/sand to 3750' and dumped 5 sacks of cement with bailer. Pulled 5 1/2" casing.  
Cleared hole and checked fluid to 600', mudded the hole to 300', set rock bridge to 290' and ran 20 sacks of cement. Mudded the hole to 40' set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETED

RECEIVED  
STATE CORPORATION COMMISSION

DEC 17 1958

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor West Supply Co., Inc. 12-17-58  
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.  
I, Noel J. Knight (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
Chase, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 5th day of December, 19 58

My commission expires 9-27-62 Notary Public.

PLUGGING  
FILE SEC. 36 T. 20 R. 16W  
BOOK PAGE 148 LINE 19

15.145.00293.0000

BRINRICH DRG. CO.

Well: Schmitt #1

NE SE NE  
Sec. 36-20-6

Commenced R.D. 8-27-55  
Completed R.D. 9-7-55

Pawnee County

Casing: 1010' 8 1/2" O.D. 28# cc  
3837' 5 1/2" O.D. 14# -100#

Elevation: 2007 RB

Contractor: Brinrich

Total Depth: ~~3836~~ 3837

| STRATA               | DEPTH | TOPS                  |
|----------------------|-------|-----------------------|
| Sur face soil & clay | 45    | Heebner 3340- 1333    |
| Clay & rock          | 70    | Brown Lime-3427- 1420 |
| Shale & gumbo        | 200   | Lansing 3439- 1432    |
| Shale                | 300   | Cong. 3699- 1692      |
| Sand                 | 540   | Simpson 3724- 1717    |
| Red Bed              | 665   | Arbuckle 3760- 1753   |
| Red Bed & Shale      | 1005  |                       |
| Gip                  | 1009  |                       |
| Anhydrite            | 1011  |                       |
| Red Bed & Shells     | 1135  |                       |
| Red Bed & Shale      | 1320  |                       |
| Shale                | 1555  |                       |
| Shale & Salt         | 1700  |                       |
| Shale & Lime         | 1835  |                       |
| Lime & Shale         | 2050  |                       |
| Lime                 | 2485  |                       |
| Lime & Shale         | 2635  |                       |
| Lime                 | 3045  |                       |
| Lime & Shale         | 3165  |                       |
| Lime                 | 3255  |                       |
| Lime & Sha,e         | 3330  |                       |
| Lime                 | 3464  |                       |
| Lime & Shale         | 3535  |                       |
| Lime                 | 3570  |                       |
| Lime & Shale         | 3597  |                       |
| Lime                 | 3650  |                       |
| Lime & Shale         | 3700  |                       |
| Lime, Shale & Chirt  | 3749  |                       |
| Lime & Shale         | 3771  |                       |
| Lime                 | 3781  |                       |
| Lime & Chirt         | 3816  |                       |
| Lime                 | 3826  |                       |
| Total Depth          | 3826  |                       |

*Ref-3760-66  
w/36 holes*

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling reports.

RECEIVED  
STATE CORPORATION COMMISSION

BRINRICH DRILLING CO., INC.  
BY

NOV 26 1958

CONSERVATION DIVISION  
Kansas

*Ralph B. McLaughlin*  
Ralph B. McLaughlin-Sec. Treas.

Signed and sworn to in my presence this 19th day of September, 1955, by Ralph B. McLaughlin, Secretary-Treasurer of the Brinrich Drilling Co., Inc., A C orporation in the State of Kansas.

*Anna S. Riley*  
Notary Public

My commission expires December 31, 1958.

PLUGGING  
FILE SEC. 36 T. 20 R. 6W.  
BOOK PAGE 146 LINE 19