

CORRECTED COPY

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-113-21,219.0000

LEASE NAME H C Stucky (B)

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

2105 Ft. from S Section Line

2270 Ft. from E Section Line

SEC. 15 TWP. 20S RGE. 3 (E or W)

COUNTY McPherson

LEASE OPERATOR S & H Oilfield Enterprises

ADDRESS RR 1 Box 35A, McPherson, Kansas 67460

PHONE# (316) 345-8405 OPERATORS LICENSE NO. 6159

Date Well Completed -

Character of Well Oil & Gas

Plugging Commenced 12/10/88

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12/10/88

The plugging proposal was approved on 12/10/88 (date)

by Merlan Unruh (KCC District Agent's Name).

Is ACO-1 filled? No If not, is well log attached? Yes

Producing Formation Mississippi Depth to Top 3061 Bottom 3105 T.D. 3154

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Mississippi	Dry	3061	3105	-	0	0
		210	0	8-5/8	210	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Drilled rotary total depth to 3154. Filled with mud to 300 ft. Set 1st plug with 40 sacks common cement. Fill with heavy mud to 60 ft. Set 2nd plug with 25 sacks common cement. Fill rathole with 10 sacks common cement.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Tornado Drilling, Inc. License No. 3890

Address P.O. Box 37, Canton, Kansas 67428

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: S & H Oilfield Enterprises (Hank Siemens)

STATE OF Kansas COUNTY OF McPherson, ss.

Terry P. Bandy, Agent

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Terry P. Bandy President

(Address) P.O. Box 37, Canton, Ks. 67428

10-25-89 OCT 25 1989

WITNESSED AND SWORN TO before me this 13th day of December, 1988

Cynthia H. Reimer
Notary Public

My Commission Expires: June 14, 1990

CYNTHIA H. REIMER
NOTARY PUBLIC
STATE OF KANSAS
EXPIRES 6-14-90

TORNADO DRILLING, INC.
P.O. BOX 37
CANTON, KANSAS 67428

December 12, 1988

COMPANY: S & H OILFIELD ENTERPRISES
CONTRACTOR: TORNADO DRILLING, INC.
FARM: H C STUCKY (B) #1
LOCATION: 2105' FSL & 2270' FEL Section 15-20S-3W
McPherson County, Kansas
COMMENCED: DECEMBER 5, 1988
COMPLETED: DECEMBER 10, 1988

ELEVATION:

0	to	70	Soil & Clay
70	to	95	Sand
95	to	229	Shale
229	to	525	Shale
525	to	910	Shale & Lime
910	to	1250	Lime & Shale
1250	to	1630	Lime
1630	to	1890	Lime & Shale
1890	to	2110	Shale & Lime
2110	to	2222	Lime & Shale
2222	to	2330	Douglas Sand
2330	to	2545	Lime & Shale
2245	to	2715	Shale & Lime
2715	to	2835	Lime
2835	to	2933	Lime & Shale
2933	to	3000	Shale & Lime
3000	to	3061	Lime
3061	to	3105	Chert Mississippi
3105	to	3154	Lime
		3154	Rotary Total Depth

RECEIVED
STATE CORPORATION COMMISSION

DEC 14 1988

CONSERVATION DIVISION
Wichita, Kansas

Drill 12 1/4" hole to 225'. Run 8-5/8" surface casing to 210', cemented with 150 sacks of cement. Plug down at 12:15 P.M., December 5, 1988. Well plugged according to the rules and regulations of the State of Kansas, Corporation Commission at 12:15 P.M., December 10, 1988. Measurements taken from K.B.

CERTIFICATE

I, Terry P. Bandy, President of Tornado Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your H C Stucky (B) #1 located on the 2105' FSL & 2270' FEL Section 15-20S-3W, McPherson County, Kansas as is reflected by the files of Tornado Drilling, Inc.

Terry P. Bandy
Terry P. Bandy, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 12th day of December, 1988.

Cynthia G. Reimer
Cynthia G. Reimer - Notary Public

