

STATE OF KANSAS
STATE CORPORATION COMMISSION

RECEIVED
MAY 5 1937
14

WELL PLUGGING RECORD
OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plugging
off formations.

All Information Complete
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

McPherson County. Sec. 15 Twp. 20 Rge. (E) 3 (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines SW 1/4 SW 1/4 SE 1/4

Lease Owner J. S. Cling

Lease Name Barg Well No. 1

Office Address 923 So. Ash, McPherson, Kansas

Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole

Date, well completed April 18 1937

Application for plugging filed April 23 1937

Application for plugging approved April 24 1937

Plugging Commenced April 24 1937

Plugging Completed April 30 1937

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 193

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Russell

Producing formation Depth to top Bottom Total Depth of Well 3613 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Refer to log				20"	104'6"	104'6"
				15 1/2"	409'	409'
				13 3/8"	1730'	1730'
				10"	2430'	2430'
				8 1/2"	3080'	3080'
				6 5/8"	3269'	3239'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with mud from 3613' to 3269' the 6 5/8" hole (jatted)

" " " " 3269' to 2980' " 8 1/2" " "

" " " " 2980' to 2360' " 10" " "

" " " " 2360' to 1400' " 13 3/8" " "

" " " " 1400' to 160' " 15 1/2" " "

Set bridge at 160' filled with dirt to 150'; with rock to 140'

Cemented to 125'; filled with mud to top; capped with cement cap

PLUGGING
FILE MAY 15 20 1937
BOOK PAGE 85 LINE 41

(If additional description is necessary use BACK of this sheet)

Correspondence regarding this well should be addressed to J. S. Cling

Address 923 So. Ash, McPherson, Kansas

STATE OF Kansas, COUNTY OF McPherson, ss.

Owner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. S. Cling

923 So. Ash, McPherson, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 3 day of May, 1937

My commission expires March 15 1941

J. S. OLING DRILLING COMPANY

WELL LOG

WELL NO. 1

Well Spudded Feb. 4, 1937
Completed April 16, 1937

S7 1/2 NW 1/4 Sec. 15-20N-3W

McPHILSON COUNTY, KANSAS

FORMATION	TOP	BOTTOM	FORMATION	TOP	BOTTOM
Cellar	0	8	Lime	1975	1980
Clay	8	30	Sandy shale	1980	1985
Sandy shale	30	90	Lime	1985	2000
Water sand	90	100	Shale	2000	2025
Yellow shale	100	115	Lime	2025	2135
Blue shale	115	175	Shale	2135	2145
Red rock	175	180	Lime	2145	2180
Blue shale	180	240	Shale	2180	2185
Blue shale	240	408	Lime	2185	2190
Lime & shell	408	495	Shale	2190	2200
Lime	495	520	Lime	2200	2235
Lime & shell	520	575	Water sand	2235	2270
Red rock	575	580	Shale	2270	2275
Lime	580	610	Sand	2275	2310
Blue shale	610	620	Sandy shale	2310	2325
Red rock	620	630	Sand	2325	2340
Lime	630	670	Shale	2340	2368
Shale	670	700	Lime	2368	2372
Lime Ft Riley	700	840	Red rock	2372	2376
Shale	840	845	Lime	2376	2387
Red rock	845	850	Shale	2387	2430
Shale	850	855	Lime	2430	2459
Shale & shells	855	945	Shale	2459	2460
Shale & shells	945	950	Lime	2460	2600
Lime	950	995	Blue shale	2600	2605
Shale	995	1107	Lime	2605	2660
Lime	1107	1125	Sandy lime	2660	2685
Shale	1125	1145	Lime	2685	2780
Lime	1145	1150	Shale <i>B/KC</i>	2780	2785
Shale	1150	1310	Lime	2785	2820
Red rock	1310	1315	Shale & shells	2820	2840
Shale	1315	1353	Redrock	2840	2842
Red rock	1353	1360	Lime	2842	2865
Shale	1360	1380	Shale	2865	2880
Red rock	1380	1385	Lime	2880	2900
Shale	1385	1395	Lime & shale	2900	3105
Lime	1395	1400	Variegated shale	3095	3095
Shale	1400	1425	Red rock	3095	3095
Red rock	1425	1435	Top chat	3095	3095
Shale	1435	1485	Chat	3095	3095
Lime	1485	1514	Lime (chatty)	3095	3121
Shale	1514	1560	Shale	3121	3290
Lime	1560	1595	Lime	3290	3506
Shale	1595	1615	Lime	3506	3560
Lime	1615	1630	Top Viola	3560	3560
Shale	1630	1645	Lime	3560	3596
Red rock	1645	1655	Green shale	3596	3603
Lime	1655	1670	Sandy lime	3603	3606
Red rock	1670	1675	Top Wilcox	3606	3606
Shale	1675	1680	Wilcox sand	3606	3613
Sandy lime	1680	1730	TOTAL DEPTH	3613	
Shale	1730	1738			
Lime	1738	1745			
Shale & lime	1745	1785			
Shale & lime	1785	1815			
Sandy shale	1815	1870			
Lime	1870	1973			
Shale	1973	1975			

Show of gas and oil 3095 to 3105

PLUGGING	
FILE	SEC-15-20-3W
BOOK	PAGE-85-LIN-41

PLUMBING
 FILE SEC 15, 20-314
 BOOK PAGE-85 LINE-41

Notary Public

My commission expires March 15, 1944

In witness whereof, I have hereunto set my official signature and affixed my notarial seal the day and the year first above written.

Be it remembered, that on this 15th day of March, 1944, before me, a Notary Public in and for said County and State, personally appeared John A. Clark, to me known to be the identical person who executed the same as John A. Clark, and voluntarily act and deed for the uses and purposes therein set forth.

County of Johnson

STATE OF KENTUCKY

John A. Clark

2 b/h 90 - 100
 1/2 b/h 745
 5 b/h 1400
 9 b/h 1485
 1680 - 1695
 1960
 H E V 2235 - 2270
 H E V 2545 - 2553
 H E V 3120 - 3135
 H E V 3180 - 3190
 H E V 3606 - 3613

WATER RECORD

20"	104.6"	104.6"
15 1/2"	409'	409'
13 3/8"	1730'	1730'
10"	2430'	2430'
8 1/2"	3080'	3080'
6 5/8"	3269'	3269'

Record from 1494 to 1730
 Underpinned from 2353 to 2430
 Record from 2737 to 3080'

PLUMBING

WATER

WATER RECORD

SECRET #2

15.113.04926.000