

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

T-20S NORTH R-3W

	24		

Locate well correctly on above
Section Plat

McPherson County, Sec. 23 Twp. 20 Rge. (E) 3 (W)
Location as "NE/CNW/SW" or footage from lines. C SE SW SW
Lease Owner Donald T. Ingling et al
Lease Name Zenger Well No. 1
Office Address 615 First Nat'l Bank Bldg., Wichita 2
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed May 11, 1960
Application for plugging filed July 15, 1960
Application for plugging approved July 15, 1960
Plugging commenced July 16, 1960
Plugging completed July 25, 1960
Reason for abandonment of well or producing formation no oil

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Cecil Jones
Producing formation Depth to top Bottom Total Depth of Well 3108 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	203	None
				4 1/2"	3079	2156'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded hole to 3060' - dumped 5 sacks cement -
bailed fluid down - set plug at 200' - set 10'
rock bridge - dumped 15 sacks cement. Left
hole open at top for water well as per instructions
from state plugger, Cecil Jones.

RECEIVED
STATE CORPORATION COMMISSION

SEP 6 1960

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor R & D CASING PULLING CO., License #236
Address Box 154, Ellinwood, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

D. T. Ingling (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

615 First Nat'l Bank Bldg., Wichita 2
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of September, 1960

My commission expires Feb. 27, 1964

Notary Public.

Donald T. Ingling et al, Lease Owner

Section 24-20-3W

Donald T. Ingling, Contractor

Location: C SE SW SW

Commenced: 5-3-60

County: McPherson

Completed: 5-12-60

Production:

Total Depth: 3084' (rotary)

Elevation: 1475 RB

Casing: 8 5/8" 203' (90 sacks cement)
4 1/2" 3079' (40 sacks cement)

Figures below indicate bottom formation

40	surface clay	2960	shale
70	sand and shale	3065	shale
140	shale	3069	shale
203	shale and shells	3084	Mississippi
540	shale and shells	3084	Total Depth
780	lime		
945	lime and shale streaks		
1000	lime and shale streaks		
1210	shale and shells		
1510	shale and shells		
1675	shale and shells		
1860	shale and shells		
1945	lime		
2010	lime		
2095	lime		
2160	lime		
2325	sand and shale		
2329	lime		
2386	shale		
2410	lime		
2440	lime		
2560	lime		
2631	lime		
2685	lime		
2748	lime		
2765	shale		
2810	shale		
2875	shale		

I certify this is a true and correct copy of the above mentioned well.

STATE OF KANSAS)
) ss.
 SEDGWICK COUNTY)

Subscribed and sworn to before me, a Notary Public, in said county and state.

M. E. Black
 Notary Public

My commission expires: Feb. 27, 1964