

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY McPherson SEC. 14 TWP. 20S RGE. 3W E/W
Location as in quarters or footage from lines:
330' WEL & 330' NSL

Lease Owner Eagle Resources, Inc.
Lease Name Reichert #3 Well No. _____
Office Address P.O. Box 352 Canton, Kansas 67428
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 11-12-81
Plugging completed 11-16-81
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Depleted
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Merlan W. Unruh
Producing formation _____ Depth to top _____ bottom _____ T.D. 3129'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	120'	none
				4-1/2"	3128 1/2'	2100'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged off bottom with sand to 3000' and set 4 sacks cement. Shot casing @2114' and pulled a total of 51 joints of pipe. Plugged well with 3 sacks hulls, 10 sacks gel, 100 sacks cement. Plugging completed.

RECEIVED
STATE CORPORATION COMMISSION

NOV 20 1981

CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor K Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Chase, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 19th day of November, 19 81

My Commission expires:



Irene Hoover
Notary Public.



Blackstone Drilling, Inc.

Box 455 • 523 West Kansas • Phone (316) 241-1250
McPherson, KANSAS 67460

February 27, 1979

COMPANY: DECKER PETROLEUM, INC.
CONTRACTOR: BLACKSTONE DRILLING, IN C.
FARM: RICHERT #3
LOCATION: 330' WEL & 330' NSL N/2NE/4 Sec. 14-20-3W,
McPherson County, Kansas
COMMENCED: February 20, 1979
COMPLETED: February 26, 1979
ELEVATION:

0	to	125	Shale
125	to	530	Shale & Lime
530	to	890	Lime & Shale
890	to	1475	Shale & Lime
1475	to	1865	Lime & Shale
1865	to	2015	Shale & Lime
2015	to	2320	Lime & Shale
2320	to	2560	Shale & Lime
2560	to	2760	Lime
2760	to	2900	Lime & Shale
2900	to	3035	Shale
3035	to	3129	Mississippi T. D.

Cut 12 $\frac{1}{2}$ " hole to 120' and run 122' of 8 5/8" surface pipe, cemented with 100 sacks of cement at 120'. Plug down at 12:30 P. M., February 20, 1979. Cut 7 7/8" hole to 3129'. Run 3132' of 4 $\frac{1}{2}$ " casing, cemented 6" off beam at 3128 $\frac{1}{2}$ " with 75 sacks of cement. Plug down at 12:30 P. M., February 26, 1979.

TOPS: MISSISSIPPI - 3035'

Measurements taken from K. B.

CERTIFICATE

I, P. E. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Richert #3, located on the 330' WEL & 330' NSL N/2 NE/4 Section 14-20-3W, McPherson County, Kansas as reflected by the files of Blackstone Drilling, Inc.


P. E. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 27th day of February, 1979.


Johnnie L. Schmidt - Notary Public

