

WELL PLUGGING RECORD

Give All Information Completely
Major Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH

Locate well correctly on above Section Plat

McPherson County. Sec. 14 Twp. 20S Rge. 3 (NW) (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE SE NW
Lease Owner Dunne & Strait Drilling Company
Lease Name Seifreid Well No. 1
Office Address 300 Schweiter Building
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 10-27 19.51
Application for plugging filed 10-29 19.51
Application for plugging approved 10-29 19.51
Plugging commenced 10-29 19.51
Plugging completed 10-29 19.51
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19.
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee, Box 597, McPherson, Kansas
Producing formation Depth to top Bottom Total Depth of Well 3057' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

15 sacks cement on bottom
Mud to 225'
10 foot rock budge
Mud to 15'
5 sacks cement - cap

RECEIVED
STATE CORPORATION COMMISSION
NOV - 6 1951
CONSERVATION DIVISION
Wichita, Kansas
11-6-51

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Dunne & Strait Drilling Company
Address 300 Schweiter Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
D. E. Dunne, Jr. (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *D. E. Dunne, Jr.*
300 Schweiter Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 5th day of November, 1951

Alvin G. Pasnacht
Notary Public.

My commission expires May 25, 1952

22-7377-9 4-49-10M
PLUGGING
FILE SEC 14 T 20 R 30
BOOK PAGE 120 LINE 28

WELL LOG

Lease: Seifreid County: McPherson
Well No.: 1 Location: SE SE NW
Lease Owner: Dunne & Strait Drilling Company Section: 14-208-3W

Commenced: October 16, 1951
Completed: October 27, 1951
Casing: 225' - 8-5/8"

- 0 - 375 Surface
- 375 - 670 Shale, lime
- 670 - 1010 Shale, shells
- 1010 - 1195 Lime
- 1195 - 1440 Shale, lime
- 1440 - 1750 Shale, shells
- 1750 - 1975 Shale, lime
- 1975 - 2125 Lime
- 2125 - 2460 Lime, shale (Lansing - 2394')
- 2460 - 2552 Lime
- 2552 - 3030 Lime, shale (K.C. - 2730')
- 3030 - 3057 Chat - (Miss - 3034')
- 3057 Total Depth
- Dry Hole

I hereby certify that the foregoing is a true and correct copy of the Well Log for the Seifreid #1 drilled by us, and completed October 27, 1951.

THE DUNNE & STRAIT DRILLING COMPANY

BY [Signature]
Partner

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

SEWED
COMMISSION
NOV - 6 1951
DIVISION
Wichita, Kansas

SUBSCRIBED AND SWORN TO, Before the Undersigned, a Notary Public, in and for the County and State aforesaid this 3rd day of November, 1951.

[Signature]
Notary Public

My Commission Expires May 25, 1952.

PLUGGING
FILE SEC 14 T 20 R 3W
BOOK PAGE 120 LINE 28