

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Mc Pherson County, Sec. 14 Twp. 20 Rge. 3 (E) (W)

Location as "NE/CNW%SW%" or footage from lines SW NW

Lease Owner George Hess

Lease Name Bonham Well No. 1

Office Address 505 N. Charles Mc Pherson, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed October 16 19 59

Application for plugging filed " 19 "

Application for plugging approved " oral 19 "

Plugging commenced " 19 "

Plugging completed " 19 "

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes-oral

Name of Conservation Agent who supervised plugging of this well Cecil Jones, Mc Pherson, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3109 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	165	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole full heavy mud to 165 ft.
Drove wooden plug to 165 ft. and dumped in 13 sacks cement.
Finished filling hole full heavy mud to within 40 ft. of cellar and dumped in 10 sacks cement-2 sacks in rat hole.

RECEIVED
STATE CORPORATION COMMISSION

OCT 22 1959

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Mallard Drilling Company

Address 419 Union National Bldg. Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick ss.
C. C. Nelson, owner Mallard Drg. (employee of owner) or (owner or operator)

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. C. Nelson

419 Union National Bldg. (Address)

SUBSCRIBED AND SWORN TO before me this 21st day of October, 19 59

Edward V. Sage Notary Public.

My commission expires March 12, 1962



COMPANY: George Hess
 CONTRACTOR: Mallard Drilling Company
 FARM: Bonham #1
 LOCATION: SW NW Sec. 14-20-3
 Mc Pherson County, Kansas
 COMMENCED: October 9, 1959
 COMPLETED: October 21, 1959

0	to	40	Shale
40	to	105	Sand
105	to	165	Shale and shells
165	to	710	Shale
710	to	930	Lime
930	to	1860	Shale and lime
1860	to	2030	Lime and shale
2030	to	2145	Lime
2145	to	2215	Lime and shale
2215	to	2345	Sand and shale
2345	to	2635	Lime and shale
2635	to	2715	Lime
2715	to	3076	Shale and lime
3076	to	3109	Shale and lime
		3109	T.D.

RECEIVED
 STATE CORPORATION COMMISSION

OCT 22 1959

CONSERVATION DIVISION
 Wichita, Kansas

Set 165 ft. of 8 5/8" surface pipe. Cemented with 110 sacks cement.

TOPS: Mississippi -- 3083

D.S.T. 3085 to 3109. 65" of salt water, little mud.

Measurements taken from R.D.B. R.D.B. 5 1/2' from ground level.

DRY, ABANDONED AND PLUGGED

C E R T I F I C A T E

I, G. C. Nelson, do hereby certify that the above and foregoing is a true and correct copy of log of the Bonham #1, Mc Pherson County, Kansas, as reflected by files of the Mallard Drilling Company.

G. C. Nelson

Subscribed and sworn to before me a Notary Public, within and for Sedgwick County, Kansas, this 21st day of October 1959.

Edward W. Sage

My commission expires March 12, 1962