

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

McPherson County, Sec. 14 Twp. 20S Rge. 3W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
NE SE NW

Lease Owner Kermit Schmidt
Lease Name Bonham Well No. 1

Office Address R#2, Canton, Kansas 67428
Character of Well (Completed as Oil, Gas or Dry Hole)

Dry Hole


Date Well completed January 12, 1978
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 19
Plugging completed January 12, 1979
Reason for abandonment of well or producing formation

Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-------------|---------|------|------|--------|--------|------------|
| Clay & Sand | | 0 | 100 | 8 5/8" | 100' | None |
| Shale | | 100' | 137' | 8 5/8" | 37' | None |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

First Plug set at 130' with 25 sacks of cement. Second plug set at 40' with 10 sacks of cement, 2 sacks in rathole. Plugging completed at 7:00 A. M., by State Pluggger, Gilbert Toman, Holyrood, Kansas.

RECEIVED
STATE CORPORATION COMMISSION

FEB 28 1979

3-16-79


(If additional description is necessary, use BACK of this sheet.)
Name of Plugging Contractor Blackstone Drilling, Inc.

MAR 16 1979

STATE OF Kansas COUNTY OF McPherson
Kermit Schmidt (employee of owner) or Kermit Schmidt (owner) or operator
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Kermit Schmidt
R#2, Canton, Kansas 67428
(Address)

SUBSCRIBED AND SWORN TO before me this 12 day of March, 1979



My commission expires Sept 30 - 79

Sam Barton
Notary Public.

DONALD J. MELLAND * GEOLOGIST

Phones: 241-1675 241-4582 * Box 783 * McPHERSON, KANSAS 67460

GEOLOGICAL REPORT

Kermit Schmidt.
Bonham # 1
NE SE NW, Sec. 14-20-3W
Field: Johnson S.
McPherson County, Kansas

January 12, 1979
Elevation: 1490 KB, 1488 DF
Conn: 1/5/79; Comp: 1/12/79
Casing: 8-5/8" @ 135'/100ax.

FORMATION TOPS

| | |
|---------------|--------------|
| Lansing | 2380 (-890) |
| Mississippian | 3044 (-1554) |
| RTD | 3100 (-1610) |

Cores: None

Drill Stem Tests: One test was taken in the Mississippian by Halliburton Services, job log attached.

Electrical Logs: None

Gas Detector: None

Measurements: Were taken from Kelly bushing, 5 feet above ground level. Drill pipe was strapped at 3062 feet - no corrections were made.

RECEIVED
STATE CORPORATION COMMISSION

FEB 28 1979

CONSERVATION DIVISION
Wichita, Kansas

FORMATION SUMMARY

MISSISSIPPIAN

3045-3051 Chert; white and greenish, leached, poor to fair pinhole porosity, show of oil, show of gas, no odor. DST # 1 condenses this zone.

3057-3062 Chert; white, sharp and leached with included buff to tan, finely crystalline dolomite, fair to good vugular porosity in leached chert and poor to fair porosity in dolomite, show of oil, show of gas, no odor. DST # 1 condenses this zone.

COPY

DET # 1 3045-3062 Tool run 30"-45"-30"-45"

Open 1 hour, fair to strong blow throughout, recovered 30 feet of mud, no gas in pipe, charts indicate low permeability.

| | | |
|------------|------|------------|
| Pressures: | IHP | 1534 psi. |
| | IFP | 10-15 psi. |
| | ICIP | 493 psi. |
| | FFP | 15-21 psi. |
| | FCIP | 483 psi. |
| | FHP | 1514 psi. |

3082-3100 Chert, white, leached, tripolitic, poor with some fair porosity, no shows of oil, no shows of gas.

RECOMMENDATIONS

Since there were no commercial shows of oil or gas in this well, it was recommended that it be plugged.

Respectfully submitted,

Donald J. Melland

DJM/s

COPY

RECEIVED
STATE CORPORATION COMMISSION

FEB 28 1979

CONSERVATION DIVISION
Wichita, Kansas

DRELLING TIME

Kernit Schmidt
Bonham # 1

Sec. 14-20-3W
NE SE NW

Elevation: 1490 AB
McPherson County, Kansas

| Depth | Time | Remarks |
|-----------|---------------------|---------|
| 2300-2310 | 1 1 1 1 1 1 1 1 1 1 | |
| 20 | 1 1 1 1 1 1 1 1 1 1 | |
| 30 | 2 2 2 2 2 2 2 2 2 2 | |
| 40 | 1 1 1 1 1 1 1 1 1 1 | |
| 50 | 1 1 1 1 1 1 1 1 1 1 | |
| 60 | 1 1 1 1 1 1 1 1 1 1 | |
| 70 | 1 1 1 1 1 1 1 1 1 1 | |
| 80 | 1 1 1 1 1 1 1 1 1 1 | |
| 90 | 2 2 2 2 2 2 2 2 2 2 | |
| 2390-2400 | 1 1 1 1 1 1 1 1 1 1 | |
| 10 | 2 2 2 2 2 2 2 2 2 2 | |
| 20 | 3 3 3 3 3 3 3 3 3 3 | |
| 30 | 3 3 3 3 3 3 3 3 3 3 | |
| 40 | 3 3 3 3 3 3 3 3 3 3 | |
| 50 | 2 2 2 2 2 2 2 2 2 2 | |
| 60 | 2 2 2 2 2 2 2 2 2 2 | |
| 70 | 2 2 2 2 2 2 2 2 2 2 | |
| 80 | 2 2 2 2 2 2 2 2 2 2 | |
| 90 | 1 1 1 1 1 1 1 1 1 1 | |
| 2490-2500 | 1 1 1 1 1 1 1 1 1 1 | |
| 10 | 1 1 1 1 1 1 1 1 1 1 | |
| 20 | 1 1 1 1 1 1 1 1 1 1 | |
| 30 | 1 1 1 1 1 1 1 1 1 1 | |
| 40 | 2 2 2 2 2 2 2 2 2 2 | |
| 50 | 2 2 2 2 2 2 2 2 2 2 | |
| 60 | 2 2 2 2 2 2 2 2 2 2 | |
| 70 | 2 2 2 2 2 2 2 2 2 2 | |
| 80 | 1 1 1 1 1 1 1 1 1 1 | |
| 90 | 1 1 1 1 1 1 1 1 1 1 | |
| 2590-2600 | 1 1 1 1 1 1 1 1 1 1 | |
| 10 | 1 1 1 1 1 1 1 1 1 1 | |
| 20 | 2 2 2 2 2 2 2 2 2 2 | |
| 30 | 2 2 3 3 3 3 3 3 3 3 | |
| 40 | 3 3 2 2 3 3 3 3 2 2 | |
| 50 | 2 2 2 2 3 3 3 3 2 2 | |
| 60 | 2 2 1 1 2 2 3 3 3 3 | |
| 70 | 1 1 1 1 1 1 2 2 2 2 | |
| 80 | 2 2 2 2 3 3 3 3 3 3 | |
| 90 | 3 3 2 2 3 3 3 3 3 3 | |
| 2690-2700 | 4 2 3 3 3 3 3 3 3 3 | |

RECEIVED
STATE CORPORATION COMMISSION
FEB 28 1979
CONSERVATION DIVISION
Wichita, Kansas

COPY

Sonnet # 1

Drilling Time

Page 2

| Depth | Time | | | | | Remarks |
|-----------|------|---|----|---|----|---------|
| 2700-2710 | 3 | 4 | 2 | 2 | 5 | |
| 20 | 2 | 2 | 1 | 2 | 1 | |
| 30 | 3 | 3 | 2 | 2 | 1 | |
| 40 | 3 | 3 | 2 | 2 | 1 | |
| 50 | 3 | 4 | 4 | 4 | 3 | |
| 60 | 4 | 4 | 6 | 5 | 6 | |
| 70 | 5 | 4 | 4 | 4 | 3 | |
| 80 | 3 | 4 | 4 | 3 | 4 | |
| 90 | 4 | 4 | 4 | 2 | 4 | |
| 2790-2800 | 5 | 5 | 5 | 5 | 4 | |
| 10 | 4 | 5 | 4 | 3 | 4 | |
| 20 | 3 | 3 | 3 | 2 | 2 | |
| 30 | 3 | 3 | 3 | 2 | 2 | |
| 40 | 4 | 4 | 6 | 5 | 4 | |
| 50 | 4 | 3 | 5 | 4 | 5 | |
| 60 | 5 | 4 | 5 | 3 | 4 | |
| 70 | 4 | 3 | 2 | 2 | 2 | |
| 80 | 4 | 4 | 4 | 4 | 4 | |
| 90 | 4 | 4 | 4 | 4 | 3 | |
| 2890-2900 | 4 | 4 | 4 | 2 | 1 | |
| 10 | 5 | 5 | 5 | 6 | 8 | |
| 20 | 9 | 9 | 9 | 5 | 5 | |
| 30 | 5 | 4 | 4 | 4 | 4 | |
| 40 | 4 | 5 | 8 | 7 | 7 | |
| 50 | 7 | 5 | 6 | 7 | 8 | |
| 60 | 3 | 5 | 2 | 1 | 2 | |
| 70 | 8 | 2 | 3 | 2 | 4 | |
| 80 | 8 | 5 | 2 | 2 | 4 | |
| 90 | 5 | 8 | 7 | 8 | 10 | |
| 2990-3000 | 6 | 4 | 4 | 6 | 2 | |
| 10 | 4 | 4 | 4 | 3 | 3 | |
| 20 | 3 | 3 | 2 | 3 | 4 | |
| 30 | 4 | 5 | 3 | 4 | 4 | |
| 40 | 3 | 2 | 3 | 3 | 5 | |
| 50 | 7 | 7 | 12 | 4 | 3 | |
| 60 | 3 | 6 | 4 | 5 | 6 | |
| 70 | 1 | 1 | 2 | 2 | 1 | |
| 80 | 7 | 7 | 8 | 6 | 4 | |
| 90 | 2 | 3 | 2 | 1 | 1 | |
| 3090-3100 | 3 | 1 | 1 | 1 | 3 | |

RECEIVED
STATE CORPORATION COMMISSION

FEB 28 1979

CONSERVATION DIVISION
Wichita, Kansas

Circ. @ 3050*
Circ. @ 3060*
Circ. & DET # 1 @ 3062*
Circ. @ 3080*
Circ. @ 3087*
Circ. @ 3100*

COPY

Blackstone Drilling, Inc.Box 455 • 523 West Kansas • Phone (316) 241-1250
McPHERSON, KANSAS 67460

January 12, 1979

COMPANY: KERMIT SCHMIDT
 CONTRACTOR: BLACKSTONE DRILLING, INC.
 FARM: BONHAM #1
 LOCATION: NE SE NW 14-20-3W,
 McPherson, County, Kansas
 COMMENCED: January 5, 1979
 COMPLETED: January 12, 1979
 ELEVATION:

| | | | |
|------|----|------|--------------|
| 0 | to | 100 | Clay & Sand |
| 100 | to | 138 | Shale |
| 138 | to | 335 | Shale & Lime |
| 335 | to | 990 | Lime & Shale |
| 990 | to | 1260 | Shale & Lime |
| 1260 | to | 2270 | Lime & Shale |
| 2270 | to | 2728 | Shale & Lime |
| 2728 | to | 2850 | Lime |
| 2850 | to | 2955 | Lime & Shale |
| 2955 | to | 3050 | Shale & Lime |
| 3050 | to | 3100 | Mississippi |
| | | 3100 | T. D. |

RECEIVED
 OIL & GAS CORPORATION COMMISSION
 FEB 28 1979
 CONSERVATION DIVISION
 Wichita, Kansas

Cut 12 $\frac{1}{2}$ " hole to 135' and run 137' of 8 5/8" surface pipe, cemented with 100 sacks of cement at 135'. Plug down at 3:30 P. M., January 5, 1979. Cut 7 7/8" hole to 3100'. Hole dry and abandoned. First plug set at 130' with 25 sacks of cement. Second plug set at 40' with 10 sacks of cement, 2 sacks in rat-hole. Plugging completed at 7:00 A. M., by Stats Plugger, Gilbert Toman, Holyrood, Kansas.

TOPS: MISSISSIPPI - 3050'

Measurements taken from K. B.

CERTIFICATE

I, P. E. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Bonham #1, located on the NE SE NW 14-20-3W, McPherson County, Kansas as reflected by the files of Blackstone Drilling, Inc.


 P. E. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 12th day of January, 1979.


 Johnnie L. Schmidt - Notary Public

