


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Rice County, Sec. 7 Twp. 20S Rge. 6W (E) (W)
Location as "NE/CNW/SW" or footage from lines C NE SW
Lease Owner National Cooperative Refinery Association
Lease Name Johannsen Well No. #1
Office Address 404 Lincoln Tower Bldg., Denver, Colorado 80203
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed September 27 19 73
Application for plugging filed September 27 19 73
Application for plugging approved September 27 19 73
Plugging commenced September 27 19 73
Plugging completed September 27 19 73
Reason for abandonment of well or producing formation D & A



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation Depth to top Bottom Total Depth of Well 3787 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	230.24'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole w/mud to 225' - 1/4 sk hulls & plug w/25 sx cement. Mud to 40' - 1/2 sk hulls & plug w/10 sx cmt. 2 sx in rathole.

RECEIVED
STATE CORPORATION COMMISSION
OCT 10 1973
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Red Tiger Drilling Company
Address 1720 Wichita Plaza, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Linda H. Dickens (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Linda H. Dickens
1720 Wichita Plaza, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of October, 19 73

My commission expires May 24, 1977
Linda C. Mowrey
Notary Public.



15.159.20475.0000

DRILLERS LOG

No. 1 Johannsen

CASING RECORD:	COMPANY:	Nat'l. Coop. Refinery Assn.	DESCRIPTION:
8-5/8" @ 230.24'	CONTRACTOR:	Red Tiger Drilling Company	C NE SW
w/175 sx cement	COMMENCED:	September 15, 1973	7-20S-6W
	COMPLETED:	September 27, 1973	Rice County,
			Kansas
TOTAL DEPTH: 3787'			

ELEVATION:

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay	0	40	
Shale	40	120	
Sand	120	135	
Redbed & Shale	135	231	
Shale & Shells	231	1000	
Shale & Lime	1000	2397	
Lime	2397	2845	
Shale & Lime	2845	2850	
Lime	2850	3390	
Chert & Lime	3390	3422	
Shale	3422	3530	
Shale & Lime	3530	3630	
Shale	3630	3655	
Sand	3655	3665	
Lime	3665	3787	

RECEIVED
STATE CORPORATION COMMISSION
OCT 10 1973
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Linda H. Dickens
Linda H. Dickens

Subscribed and sworn to before me this 1st day of October, 1973.

Linda C. Mowrey
Notary Public

My Commission Expires:

May 24, 1977

