

*[Handwritten initials]*

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 15 1961  
CONSERVATION DIVISION  
Wichita, Kansas

TO:  
J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: McPherson

Location: NW-SW-SW- Sec. 23 Twp. 20 Rge. 3 (E) (W)

Name of Field: Elyria Total Depth: 3136'

I have this date completed supervision of plugging of:

Lease Name: Krehbiel Well No. I

Operator's Full Name: Guy E. Finkle

Complete Address: 222 E. Kansas Ave. McPherson Kansas.

Plugging Contractor Art Lamb Casing Pulling Co,

Address: R.R 4. Hutchinson Kansas. License No. 440

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent?

Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 2:PM Day 3 Month 8 Year 61

The above well was plugged as follows:

Filled hole W/ sand from T.D. 3136' back to 3062' ran 5 sax cement W/ dump bailer.

Shot off and pulled 5-1/2" casing. Filled hole W/ mud from 3002' back to 220' set a 15'

rock bridge and filled hole W/ ready mix cement from 205' back to zero. 2 & 1/4 Yds.

8-5/8" surface pipe 5' below ground level.

Signed: *Cecil M. Jones*  
Conservation Division Agent

Reviewed: *Graham Harold Phillips*  
Field Supervisor

Remarks:

INVOICED  
DATE 8-16-61  
INV. NO. 4079-E  
9