


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Mc Pherson County, Sec. 23 Twp. 20 Rge. 3W (E) (W)
Location as "NE/CNW%SW%" or footage from lines NW/SW/SW
Lease Owner Guy Finkle
Lease Name Krehbiel Well No. I
Office Address 222 East Kansas Mc Pherson, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 3-26 1959
Application for plugging filed July 1961
Application for plugging approved July 1961
Plugging commenced July 29 1961
Plugging completed Aug 3 1961
Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Cecil Jones
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3136' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		2779'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged off bottom of hole with rock. Rock from 3080- to 3062'. Dumped 5 sx of cement. Mudded hole to 220'. Set 20' of rock bridge. Dumped 2 1/4 yds. Ready - Mix cement, filling to the bottom of the cellar.

RECEIVED
STATE CORPORATION COMMISSION

AUG 22 1961

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Art Lamb Casing Pulling Co.
Address P.O. Box 983 Hutchinson, Kansas

STATE OF Kansas, COUNTY OF McPherson, ss.
Guy E. Finkle, M. D. (employee-of-owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Guy E. Finkle M.D.*
E. Kansas and McPherson, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of August, 19 61

[Signature]
Notary Public.

My commission expires MY COMMISSION EXPIRES SEPT. 22, 1963.

WELL LOG - PETER O. KREMBIERL NO. 1

Guy E. Finkle et al, Lease owner

Section 23-20-3W

Donald T. Ingling, Contractor

Location: NW SW SW

Commenced: 3-17-59

County: McPherson

Completed: 3-26-59

Elevation: 1494 FE

Total Depth: 3103' (rotary)

Production:

Casing: 8 5/8" 200' (90 sacks bulk cement)
5 1/2" 3005' (50 sacks bulk cement)

Figures below indicate bottom formation

55	shale and surface clay	2900	lime and shale
110	sand	2965	shale and lime streaks
180	shale and shells	3065	shale and lime
200	lime shells	3071	weathered Mississippi
450	shale and shells	3103	Mississippi
480	lime and shale	3103	Total Depth
720	lime		
900	lime		
1150	shale and lime		
1225	shale and lime		
1390	shale and shells		
1565	shale and shells		
1835	shale and lime shells		
1935	lime		
2010	lime		
2110	lime		
2200	lime		
2353	sand and shale		
2357	lime - Brown		
2370	shale		
2442	lime		
2525	lime		
2625	lime		
2665	lime		
2750	lime		
2765	lime		
2830	shale		

NOTARIAL COMMISSION
JUL 27 1961
CONSTITUTION DIVISION
Topeka, Kansas

I certify this is a true and correct copy of the above mentioned well.

STATE OF KANSAS)
) ss.
SEDGWICK COUNTY)

D. T. Ingling

Subscribed and sworn to before me, a Notary Public, in said county and state.

W. E. Black
Notary Public

My commission expires: Feb. 27, 1960