

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15113.20787.0000

LEASE NAME Krehbiel

WELL NUMBER #1

SPOT LOCATION C W/2 SW/4 SW/4

SEC. 34 TWP. 20 RGE. 3W (E) or (W)

COUNTY McPherson

Date Well Completed 10-26-80

Plugging Commenced 2-20-86

Plugging Completed 2-27-86

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Excalibur Production Co., Inc.

ADDRESS Box 278 McPherson, Kansas 67460

PHONE # (316) 241-1265 OPERATORS LICENSE NO. 5330

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Salina, Kansas

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3381'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	149'	none
				5-1/2"	3380'	2406'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Plugged off bottom with sand to 2880' and 5 sacks cement. On last baylor of cement, baylor hung up on bottom, couldn't get loose so left in hole. Shot casing @2614', 2406', layed down 61 joints (2406') of 5-1/2" casing. Set rock-bridge @350' and ran 5-1/2 yards of ready-mix cement. Plugging Complete. (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050  
Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed with me the same are true and correct, so help me God.

MAR 5 1986

(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Kansas 67524

CONSERVATION DIVISION  
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 4th day of March, 1986

Irene Hoover  
Notary Public

My Commission expires:



# Blackstone Drilling, Inc.

Box 1184 • 529 West Kansas • Phone (316) 241-1250  
McPHERSON, KANSAS 67460

October 27, 1980

COMPANY:

EXCALIBUR PRODUCTION CO., INC.

CONTRACTOR:

BLACKSTONE DRILLING, INC.

FARM:

KREHBIEL #1

LOCATION:

C W/2 SW/4 SW/4 Section 34-20-3W,  
McPherson County, Kansas

COMMENCED:

October 14, 1980

COMPLETED:

October 26, 1980

ELEVATION:

0	to	60	Clay & Shale
60	to	110	Sand
110	to	160	Shale
160	to	815	Shale & Lime
815	to	1275	Lime & Shale
1275	to	1825	Shale
1825	to	2390	Lime & Shale
2390	to	2610	Shale & Lime
2610	to	2755	Lime & Shale
2755	to	2930	Lime
2930	to	2988	Shale & Lime
2988	to	3070	Mississippi
3070	to	3139	Lime & Shale
3139	to	3345	Shale
3345	to	3357	Lime
3357	to	3379	Viola
3379	to	3381	Stinson Sand
		3381	T. D.

Cut 12 1/2" hole to 149' and run 151' of 8 5/8" surface casing, cemented with 150 sacks of cement at 149'. Plug down at 10:30 A. M., October 14, 1980. Run 3384' of 5 1/2" casing, set 1 foot off bottom at 3380' with 100 sacks of cement. Plug down at 6:15 P. M., October 26, 1980.

TOPS: VIOLA - 3345'

Measurements taken from R. D.

### CERTIFICATE

I, P. E. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Krehbiel #1, located on the C W/2 SW/4 SW/4 Section 34-20-3W, McPherson County, Kansas as reflected by the files of Blackstone Drilling, Inc.

*P. E. Plouffe*  
P. E. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 28th day of October, 1980.

*Johnnie L. Schmidt*  
Johnnie L. Schmidt - Notary Public

JOHNNIE L. SCHMIDT  
McPherson County, Kansas  
My Comm. Exp. July 23, 1981