

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

**Locate well correctly on above
Section Plat**

Rice County, Sec. 15 Twp. 20 Rge. 6 (E) W (W)
Location as "NE/CNW/SW" or footage from lines C NE SW
Lease Owner Plains Exploration Co.
Lease Name Fry Well No. H #1
Office Address 1135 Petroleum Club Bldg., Denver, Colo.
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed November 26, 1965
Application for plugging filed August 8, 1967
Application for plugging approved August 10, 1967
Plugging commenced September 9, 1967
Plugging completed September 27, 1967
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production May 1967
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation Mississippi Depth to top 3323' Bottom _____ Total Depth of Well 3358' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded back to 3300' and dumped 5 sacks of cement. Shot pipe off at 2964.60'. Pulled pipe and mudded hole to 210'. Set rock bridge and dumped 25 sacks of cement. Finished mudding hole and dumped 10 sacks of cement at top of surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Bert Self

Address Hutchinson, Kans.

Kansas, COUNTY OF Reno, ss.

Employee (employee of owner) or (owner or operator) of the above-described
on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
ed and that the same are true and correct. So help me God.

(Signature)

R. R. #4, Hutchinson, Kans.

(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of September, 19 67

My commission expires October 18, 1969

Notary Public.

PLAINS EXPLORATION COMPANY
DENVER 2, COLORADO

WELL LOG -----Fry "H" # 1

LOCATED: C NE SW Section 15-20S-6W, Rice County, Kansas.

OWNER: Plains Exploration Company

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: November 13, 1965 (w/r)

COMPLETED: November 17, 1965 (w/r)

ROTARY TOTAL DEPTH: 3330'.

RECEIVED
OIL CORPORATION COMMISSION
AUG 10 1967
CONSERVATION DIVISION
Wichita, Kansas

LOG

0 - 40 Shale
40 - 90 Lime
90 - 170 Shale & Lime
170 - 550 Shale & Red Bed
550 - 875 Shale & Shells
875 - 1300 Lime & Shale
1300 - 1530 Lime
1530 - 2341 Lime & Shale
2341 - 2400 Broken Lime
2400 - 3330 Lime T.D.
TOP OF MISSISSIPPI 3323' (-1715')
C.T.T.D. 3358'.

CASING RECORD

Ran 4 joints 8 5/8" casing. 160' pipe set at 168' K.B., cemented with 14 5' sacks 50 x 50 Pozmix with HA-5. Plug was down at 6:45 p.m. November 13, 1965.

Ran 106 joints 5 1/2" used seamless casing, 3335.38' pipe set at 3329' K.B., cemented with 50 sacks regular cement. Plug was down at 6:35 a.m. November 18, 1965.

November 22, 1965: Commenced with cable tools. Drilled to 3342'.

November 24, 1965: Drilled to 3358'. Completed with cable tools.

November 26, 1965: In 41 hours, hole gave up 117 gallons water with scum of curds or lumpy, sticky grease. No live oil odor.

July 1, 1966: Frac'd with 32,820 barrels of water. Put well on pump to test. Well producing approximately 8 B.O.P.D.

E. E. Duncan