


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

## WELL PLUGGING RECORD

NORTH

Locate well correctly on above  
Section Plat

Rice

County. Sec. 15 Twp. 20 Rge. 6 (E) W (W)

Location as "NE/CNW/SW" or footage from lines C-SE-NE  
Lease Owner Plains Exploration Co.  
Lease Name Conrad Well No. 1  
Office Address Hutchinson, Kans.  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed March 23, 19 65  
Application for plugging filed February 26, 19 68  
Application for plugging approved February 28, 19 68  
Plugging commenced April 8 19 68  
Plugging completed April 16 19 68  
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production January 19 67  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3350 Feet  
Show depth and thickness of all water, oil and gas formations.

## OIL, GAS OR WATER RECORDS

## CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled back in the 5 1-2" with sand and gravel to 3300'. Dumped 5 sacks of  
cement. Shot pipe off at 3068.65'. Pulled pipe and mudded hole to 200'.  
Set rock bridge and dumped 25 sacks of cement. Finished mudding hole and  
dumped 10 sacks of cement at base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
APR 22 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor Bert Self (If additional description is necessary, use BACK of this sheet)  
Address Hutchinson, Kans.

Kans.

Employee

COUNTY OF Reno, ss.

(employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filled and that the same are true and correct. So help me God.

(Signature)

Bert Self  
R. R. #4, Hutchinson, Kans.

(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of April, 19 68

My commission expires

October 18, 1969

Notary Public.

STERLING DRILLING COMPANY  
Sterling, Kansas

WELL LOG LOCATED: C SE NE Section 15-20S-6W, Rice County, Kansas Conrad #1

OWNER: Plains Exploration Company  
ROTARY DRILLING CONTRACTOR: Group Exploration Company

COMMENCED: March 7, 1965  
COMPLETED: March 13, 1965

ROTARY TOTAL DEPTH: 3316'

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 28 1968  
CONSERVATION DIVISION  
Wichita, Kansas

LOG

0 - 75	Lime Redbed
75 - 645	Shale & Shells
645 - 1360	Lime & Shale
1360 - 1570	Lime
1570 - 2260	Lime & Shale
2260 - 2540	Lime
2540 - 2665	Lime & Shale
2665 - 2784	Sand & Shale
2784 - 3250	Lime
3250 - 3296	Lime & Shale
3296 - 3316	Mississippi Lime T.D.

CASING RECORD

Ran 6 joints 8-5/8" 32# used seamless casing. 166' pipe set at 174' K.B., cemented with 150 sacks Pozmix #1 with 2% HA-5.

Ran 10 joints 5-1/2" casing, cemented at 3315' K.B. with 50 sacks common cement. Plug down at 3:00 p.m.