

E. J. SHAFFER CONTRACTOR

Rotary Commenced 5/4/40
 Rotary Completed 5/25/40
 Cable Tool Commenced 5/28/40
 Cable Tool Completed 6/2/40 June 3, 1940

Conrad #1 Well
 Sec 15 Twp 20 Rge 6
 Rice County, Kansas

0-40	Surface Clay
45	Clay and Shells
116	Red Rock and Shells Surface Pipe Set
350	Red Rock and Shells
550	Anhydrate and Shale and Shells
865	Shale and Salt
930	Lime and Shale
954	Anhydrate
1240	Shale and Shells
1290	Sandy Shale
1395	Sandy Lime
1660	Shale and Lime
2005	Sandy Lime and Shale
2180	Shale and Lime
2195	Shale
2292	Shale and Lime Sandy
2600	Lime
2695	Sandy Lime
2710	Lime and Shale
2800	Shale
2808	K.C. Lime (Porous)
2900	Lime
2940	Lime (Porous)
2960	Lime
3025	Lime and Shale
3075	Lime
3309½	Shale and Lime
3388	Chat
3390 T. D.	Black Shale H.F.W.

SURFACE STRING:

Run 116' of 10½" 8thd Casing cemented with 75 sacks of Lone Star Cement.
 Completed at 8:45 A.M.

OIL STRING

Run 3309½' of 7" 8thd Casing, over all measurment 3326'. Cemented
 with 75 sacks of Lone Star Cement. Completed at 10:00 P.M.

State of Kansas) ss
 County of Reno))

I, the undersigned, being duly sworn on oath, state that the
 above and within statement is a true and correct record and log of
 the well drilled on the location aboved described, to the best of
 my knowledge and belief.

George W. Shaffer Jr.
 George W. Shaffer Jr.

Subscribed and sworn to before me this 5th day of June, 1940
 My Commission expired Apr 2, 1941

Emelyn Hanson
 NOTARY PUBLIC

