


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. E. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Rice County. Sec. 9 Twp. 20S Rge. 6W (E) (W)
Location as "NE/CNW/SW" or footage from lines NE NE SE
Lease Owner Cherry Drilling Co., Inc.
Lease Name Rose Well No. 1
Office Address 102 Insurance Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 17, 1958
Application for plugging filed October 17, 1958
Application for plugging approved October 17, 1958
Plugging commenced October 17, 1958
Plugging completed October 17, 1958
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert J. Toman, Holyrood, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3627 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 200 feet. Set bottom plug with 1/4 sack hulls and 20 sacks cement through drill pipe. Filled with heavy mud to 35 feet. Set top plug with 1/4 sack hulls and 10 sacks cement. Used 2 sacks cement to plug rat hole and put cap on surface pipe.

RECEIVED
STATE CORPORATION COMMISSION
OCT 24 1958
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Cherry Drilling Co., Inc.
Address 102 Insurance Building, Wichita 2, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Betty Brandt (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Betty Brandt, Secretary
102 Insurance Building, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of October, 19 58

My commission expires July 25, 1960.
Lorraine Colaw
Lorraine Colaw Notary Public.

PLUGGING
FILE SEC 9 T 20 R 6W
BOOK PAGE 137 LINE 43

15.159.00231.0000

CHERRY DRILLING CO., INC.
102 INSURANCE BUILDING
WICHITA 2, KANSAS

ROTARY DRILLING LOG

Lease:	Rose	Company:	Cherry Drilling Co., Inc. 102 Insurance Building Wichita 2, Kansas
Well No.:	1		
Location:	NE NE SE Section 9-20S-6W Rice County, Kansas	Contractor:	Cherry Drilling Co., Inc.
Elevation:	1575 D. F. 1572 Gr.	Geologist:	R. W. Frensley 102 G Insurance Building Wichita 2, Kansas
Well Commenced:	10- 6-58	Surface Pipe:	11 Jts. used 8-5/8" - 219.68' overall less threads cemented with 150 sacks common cement, 2% CC
Well Completed:	10-17-58	Casing:	D & A

0 - 217	Shale shells	2550 - 2725	Shale, sand & lime
217 - 635	Shale, red bed, shells	2725 - 3020	Lime & shale
635 - 990	Lime & shale	3020 - 3145	Lime
990 - 1240	Shale & lime	3145 - 3286	Lime & shale
1240 - 1460	Lime & shale	3286 - 3305	Chert lime
1460 - 1690	Shale & shells	3305 - 3335	Lime & shale
1690 - 1975	Shale	3335 - 3440	Shale & lime
1975 - 2200	Shale & lime	3440 - 3545	Shale
2200 - 2320	Shale & shells	3545 - 3590	Lime
2320 - 2410	Shale & lime	3590 - 3627	Lime & sand
2410 - 2550	Lime	3627	R. T. D.

GEOLOGIST'S TOPS

Heebner	2567 (- 989)	Mississippi Lime	3306 (-1728)
Toronto	2585 (-1007)	Kinderhook	3317 (-1739)
Douglas sand	2610 (-1032)	Maquoketa	3556 (-1978)
Brown Lime	2735 (-1157)	Viola	3566 (-1988)
Lansing	2756 (-1178)	Simpson sand	3595 (-2017)
Mississippi Chat	3265 (-1687)	R. T. D.	3627 (-2049)

The above is a true and correct log to the best of my knowledge.

RECEIVED
 STATE COMMISSION
Betty
 Secretary

OCT 21 1958

Subscribed and sworn to before me this 20th day of October, 1958.

PLUGGING

FILE SEC 9 T 20 R 6W

BOOK PAGE 137 LINE 43

CONSERVATION DIVISION
 Wichita, Kansas
Lorraine Colaw
 Lorraine Colaw Notary Public

My Commission Expires: July 25, 1960.