

15-097-19039-000

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Kiowa SEC. 25 TWP. 28S RGE. 19 E/W  
 Location as in quarters or footage from lines:

		25	
			x

Lease Owner TGT Petroleum Corp.  
 Lease Name Vieux Well No. 1  
 Office Address 209 E. William - Wichita, Ks. 67202  
 Character of Well (Completed as Oil, Gas or Dry Hole): Core Hole  
 Date Well Completed 2-18-82  
 Application for plugging filed \_\_\_\_\_  
 Plugging commenced 1:15 PM 4/6/82  
 Plugging completed 2:00 PM 4/6/82  
 Reason for abandonment of well or producing formation \_\_\_\_\_

Locate Well  
 correctly on above  
 Section Platt.

Lost 700' 2 7/8" drill pipe in hole  
 Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 1240

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				5 1/2"	208	Cemented surface

Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_  
 feet to \_\_\_\_\_ feet for each plug set.

Inject 2 sacks gel, 2 sacks hulls into 5 1/2" surface casing on top of 40 visc mud. Then  
pump 60 sacks Halliburton common, 3% cc on top of that. Clear valve, swedge & landing  
nipple with clear water (1/3 bbl), shut in valve. Shut in pressure - 600 psi.  
Leaving cement plug from 10-15' to 700'.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor TGT Petroleum Corp.

STATE OF Kansas COUNTY OF Sedgwick, ss.  
B. Lynn Herrington (employee of owner) or (owner or operator) of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.

RECEIVED  
 STATE CORPORATION COMMISSION

(Signature) B. Lynn Herrington  
209 E. William-Wichita, Ks.  
 (Address)

SUBSCRIBED AND SWORN TO before me this 20th day of April, 19 82

CONSERVATION DIVISION  
 Wichita, KANAS

Judith K. Moser  
 Judith K. Moser Notary Public.

My Commission expires: May 17, 1985

