

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-097-20756-000

LEASE NAME Thomas

WELL NUMBER A#1

SPOT LOCATION C NE NE

SEC. 25 TWP. 28 RGE. 19 (E) or (W)

COUNTY Kiowa

Date Well Completed 9-28-81

Plugging Commenced 5-23-88

Plugging Completed 5-26-88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Aspen Oil Inc.

ADDRESS No Address---Bankrupt

PHONE # (316) 675-8349 OPERATORS LICENSE NO. 6497

Character of Well Oil & Gas
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes If not, is well log attached? _____

Producing formation Miss. Depth to top 4919 bottom 4938

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled |
|------------|---------|------|----|--------|--------|--------|
| Surface | | | | 8 5/8" | 307 | 0' |
| Production | | | | 4 1/2" | 4962 | 3230' |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Pump 2 Sks. hulls & 20 sks. cement to 4700' - pressured to 700 lbs. Mud to 720' - Pump 50 Sks. cement 720' to 575' Mud to 330' - Pump 40 sks. cement 330' to 230'
Cut off 3' below ground level & cap

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing Pulling License No. 6497
Address Box F, Sublette, Ks. 67877

STATE OF KANSAS COUNTY OF HASKELL, ss.

I, Edgar J. Eves (~~XXXXXXXXXXXXXXXXXXXX~~) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Edgar J. Eves

(Address) Box F, Sublette, Ks 67877

SUBSCRIBED AND SWORN TO before me this 29 day of June, 1988

Sandra L Eves
Notary Public

My Commission expires: 12-6-88

