

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-007-01395-00-01

API NUMBER Drilled in 1951

LEASE NAME Boggs "C"

WELL NUMBER 14

990 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 17 TWP. 33 RGE. 12 ~~W~~ W

COUNTY Barber

Date Well Completed 8-20-51

Plugging Commenced 5-13-86

Plugging Completed 5-16-86

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Frank J. Black

ADDRESS Box 250 -McPherson, Ks. 67460

PHONE# (316) 241-2624 OPERATORS LICENSE NO. 5357

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District # 1

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation simpson sand Depth to Top 4873 Bottom 4930 T.D. 4930

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	600	8 5/8		0
		0	4875	5 1/2		0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pump 5 1/2 with 2 hulls, 30 sxs. 60/40 poz., 20 sxs. gel, & 65 sxs. cement.  
Fill Annulus with 35 sxs. cement, through 1" pipe. & Fill 5 1/2 with  
another 120 sxs. cement, as first plug slipped.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Nicholas Casing Pulling License No. 6698

Address 420 5th. -Geneseo, Kansas 67444

STATE OF Kansas COUNTY OF Rice, ss.

Allen D. Nicholas (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Allen D. Nicholas

(Address) 420 5<sup>th</sup> Geneseo, Ks 67444

SUBSCRIBED AND SWORN TO before me this 20th day of May, 19 86

Joni L. Prickett  
Notary Public

My Commission Expires: December 25, 1988

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 22 1986  
CONSERVATION DIVISION  
Wichita, Kansas

5-22-1986

TONI L. PRICKETT  
State of Kansas  
My Appt. Exp. 12-25-88

STENCILED

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
503 East Murdock,  
Wichita, Kansas

CONV. SERIAL  
15-007-01395-00

NOV 24 1951

Company- SKELLY OIL CO.  
Farm- Böggs "C" No. 14


SEC. 17 T. 33 R. 12W

NW SE SE

990' fr EL 990' fr SL SE 1/4

County Barber  
KANSAS

Total Depth. 4930  
Comm. 7-28-51 Comp. 8-20-51  
Shot or Treated.  
Contractor. Chas. Hulme Drlg. Co.  
Issued. 11-24-51



Elevation. 1575 DF

Production. Pot. 329 bbls.

Figures Indicate Bottom of Formations.

surface soil, clay, & shale	165
red bed, shale & shells	600
shale	1315
shale, salt & shells	1630
shale & lime	1965
lime	2010
sandy lime	2115
lime & shale	2270
sandy lime	2455
shale	2505
lime	2630
lime & shale	3075
lime	3210
lime & shale	3300
lime	3510
lime & shale	3565
shale	3615
limo	3640
sandy lime	3725
shale	3780
shale, lime & sand	3845
sandy lime	3870
fine grained slightly porous sand	3912
lime	4118
lime & shale	4140
lime	4235
shale & lime	4315
lime	4766
medium grained friable sand	4771
lime & shale	4795
lime	4815
sandy lime	4827
lime & shale	4850
cherty lime	4860
lime & sand	4873
fine to medium grained porous sand	4914
fine grained slightly porous hrd sand	4930
Total Depth	

Trace of oil stain 4914-4930'

Producing Formation Simpson Sand 4875-4930'

Shot 92 qts. at 4885-4930'

K. G. S. LIBRARY

Tops:

Elgin Sand	3625
Douglas Sand	3870
Lansing Lime	3912
Mississippi Lime	4490
Kinderhook Shale	4659
Misener Sand	4766
Viola Lime	4771
Simpson Shale	4868
Simpson Sand	4873

no shows 3870-3912'  
Good porosity and light oil stain 4766-4771'  
Light oil stain 4873-4914'

RECEIVED  
STATE CORPORATION COMMISSION

OCT 10 1955

CONSERVATION DIVISION  
Wichita, Kansas