

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Kiowa County, Sec. 14 Twp. 28 Rge. 20 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NW NW NW
Lease Owner Imperial Oil of Kansas
Lease Name McDonald Well No. 1
Office Address Union National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 1/22 19 56
Application for plugging filed 1/22 19 56
Application for plugging approved 1/22 19 56
Plugging commenced 1/22 19 56
Plugging completed 1/22 19 56
Reason for abandonment of well or producing formation Dry Hole

NORTH

Section Plat grid with 'X' in the top-left cell.

Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation Depth to top Bottom Total Depth of Well 5023 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULLED OUT. Row 1: SIZE 8 5/8, PUT IN 710', PULLED OUT None.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

First plug set @ 300' with 20 sacks cement

Second plug set @ 35 feet with 10 sacks cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Schafer Drilling Co.
Address Box 350, Pratt, Kansas

STATE OF Kansas, COUNTY OF Pratt, ss.
Lou Guthridge (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lou Guthridge
Pratt, Kansas (Address)

Subscribed and Sworn to before me this 23rd day of Jan 19 56

My commission expires May 16, 1959

24-7368-S 3-53-20M

PLUGGING
FILE SEC 14 T 28 R 20 W
BOOK PAGE 33 LINE 34

Notary Public
1-24-56

DRILLERS LOG
McDONALD #1
KIOWA COUNTY, KANSAS

0-90	Sand and Gravel
90-575	Sand and Clay
575-710	Shale and Shell
710-1205	Shale and Red Bed
1205-2100	Shale and Shell
2100-2490	Shale and Lime Shell
2490-4315	Lime and Shale
4315-4390	Lime
4390-4949	Lime and Shale
4949-5023	Lime, Shale and Chert
5023	TOTAL DEPTH

I certify that the above drillers log is true and correct as taken directly from the daily drilling reports of the McDonald #1.


Law Guthridge
Schafer Drilling Co.

State of Kansas: County of Pratt: SS

The above was subscribed and sworn to before me this 23rd day of January, 1956.

Marilyn Guthridge
Notary Public

My commission expires *May 16, 1959*



RECEIVED
STATE OF KANSAS CONSERVATION DIVISION
JAN 27 1956
CONSERVATION DIVISION
Wichita, Kansas