

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-097-20,828

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Petro-Dynamics Corp.

Complete Address 555 N. Woodlawn Bldg 1 Suite 207 Wichita Kansas 67208

Lease Name Sloan Well No. 1

Location C-NE-NW Sec. 31 Twp. 28 Rge. 19 (East)(West)

County Nowa Total Depth 5100'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated This well was completed but never produced

Plugging Contractor Nelson Casing Pullers

Address Box 176 Chas Kansas 67524 License No. 681

Operation Completed: Hour: 5:30 PM Day: 8 Month: July Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

They had 1177' of 8 5/8" cemented with 150 sby of Superite Cement. They set 5098' of 4 1/2" production pipe cemented with 110 sby. They plugged back the 4 1/2" to 5001' perforated from 4985' to 5000'. 1st plug sand bottom back to 4930' dumped 4 sby of cement on top of sand with bailer. 2nd pumped down through sawedge or 10 3/4", 10 sby gell 5 sby hulls & 15 sby gell and 200 sby of cement. The cement used was 50/50 Pass with 2% gell & 3% cc cement. They re opened 3843' of 4 1/2" (grey)
Amount of Surface Casing: 10 3/4 - 284' circulated with 250 sby of cement

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luthin
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION
JUL 13 1982
CONSERVATION DIVISION
Wichita, Kansas

Signed: _____
Conservation Division Agent

INVOICED

DATE 7-13-82
INVOICE 622-W

production pipe. Then they recovered none' of $8\frac{5}{8}$ "
pipe. The Plugging was accomplished by
Allied Cementing.

Paul Luthi

ALLIED CEMENTING CO.
1000 W. 10th St.
OILFIELD DIVISION
DALLAS, TEXAS