

70
KANSAS
STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT JUL 20 1961

CONSERVATION DIVISION
Wichita, Kansas

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Rice

Location: SW- NE- SW- Sec. 23 Twp. 20 Rge. 6 KEA (W) _____

Name of Field: Bornholdt Total Depth: 3347'

I have this date completed supervision of plugging of:

Lease Name: Hubenett Well No. 3

Operator's Full Name: Frank J. Black

Complete Address: P.O.Box 150, McPherson Kansas.

Plugging Contractor R. & D. Casing Pulling Co.

Address: P.O.Box 572, Hutchinson Kansas. License No. 236

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 5:PM Day II Month 7 Year 61

The above well was plugged as follows:

Filled hole w/ sand from T.D. 3347' back to 3312' ran 5 Sax cement w/ dump bailer.

Shot off and pulled 5-1/2" casing. Filled hole w/ mud from 3277' back to 210' set a

10' rock bridge and 20 sax cement. Filled hole w/ mud from 140' back to 35' set 5' rock

bridge and 8 sax cement. back to zero. 8-5/8" surface pipe 5' below ground level.

Signed: Booil W. James
Conservation Division Agent

Reviewed: Graham Harold Ellis
Field Supervisor

Remarks:

INVOICED

DATE 8/4/61

INV. NO. 3491-W