



ROBERT B. DOCKING Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
DALE E. SAFFELS Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 29 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Armstrong of Armstrong & Jackman has this date requested permission to plug the following described well:

Mr. Armstrong guarantees payment of the plugging fee.

Operator's full Name: Armstrong & Jackman

Complete Address: 655 Fourth Natl. Bk. Bldg. Wichita, Kansas

Lease Name: Niehage Well No. # 1

Location: NW SW NW Sec. 34 Twp. 20S Rge. 3 (E)(W)

County: McPherson Total Depth 3497' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Armstrong was instructed to plug the well as follows:

8 5/8"-218'-Circulated w/cement.

Mud 3497' to 200'. Plug, Hulls, 25 Sax. cement 200' to 125'.

Mud 125' to 40'. Plug, Hulls, 10 Sax. cement 40' to 0.

Very truly yours,

  
Conservation Division Agent