

State of Kansas



15.159.19435.0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

September 13, 1967

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

OCT 2 1967

Dear Sir:

Mr. Bert Self of Self Casing Pulling Co. has this
date requested permission to plug the following described well:

Mr. Self guarantees payment of the plugging fee.

Operator's full Name: Plains Exploration Company

Complete Address: 1135 Petroleum Club Bldg., Denver, Colorado 80202

Lease Name: Fry "H" Well No. 1

Location: C NE SW Sec. 15 Twp. 20 Rge. 6 (E) (W) X

County Rice Total Depth 3358' Oil Well X


Gas Well Input Well SWD Well D & A Lost Hole

Mr. Self was instructed to plug the well as follows:

Fill hole with sand to 3300' and cement with 5 sacks.

Fill hole with mud to 210'. Set rock bridge from 210' to 200' and
cement hole with 25 sacks. Fill hole with mud to 40'. Set rock bridge
from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,


Conservation Division Agent