

State of Kansas



15.159.30279.0000

State Corporation Commission

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

FEB 9 1967

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
CONSERVATION DIVISION
WICHITA, KANSAS

January 31, 1967

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Bert Self of Self Casing Pulling Co. has this

date requested permission to plug the following described well:

Mr. Self guarantees payment of the plugging fee.

Operator's full Name: Plains Exploration Company

Complete Address: 1135 Petroleum Club Bldg., Denver, Colorado

Lease Name: Conrad Well No. 2

Location: C NE NE Sec. 15 Twp. 20 Rge. 6 (E) (W) X

County Rice Total Depth 3357' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Self was instructed to plug the well as follows:

Fill hole with sand to 3300' and cement with 5 sacks.

Fill hole with mud to 210'. Set rock bridge from 210' to 200' and

cement hole with 25 sacks. Fill hole with mud to 40'. Set rock bridge

from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

Conservation Division Agent