

State of Kansas



15.159.30283.0000

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

February 18, 1969

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 24 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bert Self of Self Casing Pulling Company has this date requested permission to plug the following described well:

Mr. Self guarantees payment of the plugging fee.

Operator's full Name: Plains Exploration Company

Complete Address: 1135 Petroleum Club Bldg., Denver, Colorado 80202

Lease Name: Fry "I" Well No. 1

Location: C NW NE Sec. 23 Twp. 20 Rge. 6 (E) (W) X

County: Rice Total Depth 3324' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Self was instructed to plug the well as follows:

Fill hole with sand to 3355' and cement with 5 sacks cement.

Fill hole with mud to 210'. Set rock bridge from 210' to 200' and

cement hole with 25 sacks cement. Fill hole with mud to 40'. Set rock

bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

W. L. D. Thomas
Conservation Division Agent