

To: 1 120769 1-27  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-145-21,342.0000 63R  
NW NE NW, SEC. 36, T 20 S, R 16 WXX  
4950 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5418  
Operator: Allen Drilling Company  
Name & Address: 6565 S. Dayton St., Ste. 3800  
Englewood, CO 80111-6137

Lease Name Franklin Trust Well # 1-36  
County Pawnee  
Well Total Depth 3905 126.91 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1034

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050  
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9:30 a.m. Day: 27 Month: 1 Year: 1993

Plugging proposal received from Manny  
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

logs: 5 1/2" at 3903', Perfs at 3760-62, 3765-67'  
1st plug sand back to 3700' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 12:30 p.m. Day: 27 Month: 1 Year: 1993

ACTUAL PLUGGING REPORT 1st plug sanded back to 3700' and dumped 5 sx cement on top of sand through bailer,  
2nd plug pumped into 8 5/8" with 250 lbs. hulls, 14 sx gel, 50 sx cement, 6 sx gel, 150 lbs. hulls, and 200 sx cement.  
Pumping pressure 1300 psi and shut in 900 psi.

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. Recovered 2929' of 5 1/2" casing.

INVOICED  
DATE 2-4-93  
INV. NO. 37305

Signed Oscar Rankin (TECHNICIAN)

75-1

RECEIVED  
STATE CORPORATION COMMISSION

FEB - 1 1993  
CONSERVATION DIVISION  
WICHITA, KANSAS

3777  
FEB 1 1993