

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-21170-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 15-20S-3W
2970 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: STUCKEY Well Number: 1-B
County: MCPHERSON Total Vertical Depth: 3700 feet

Operator License No.: 6159
Op Name: SIEMENS, HANK DBA S & H OILFIELD E
Address: PO BOX 168
MOUND RIDGE, KS 67107

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 221 135 SX CMT 120.25
Production: Size 5.5 feet: 3211 100 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/21/2002 2:00 PM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: HANK SIEMENS Company: HANK SIEMENS DBA/S & H OILFIE Phone: (620) 345-8405

Proposed Plugging Method: Sand to 3,010' and spot 5 sxs. cement. Shoot pipe off. Pull pipe to 525' and spot 35 sxs. cement. Pull pipe to 325' and circulate cement to the surface.

Plugging Proposal Received By: MICHAEL WILSON

Witness Type: Plugging Operations Partially Witnessed

Date/Time Plugging Completed: 01/21/2002 4:00 PM

KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Sanded to 2,972' and topped with 5 sxs. cement. Shot casing off at 1,820'. Pulled casing to 525' and spotted 35 sxs. cement. Pulled casing to 325' and circulated 165 sxs. cement to the surface. Topped with 38 sxs. cement on 01/23/02.

RECEIVED
KCC DISTRICT #2

FEB 07 2002

WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY UNITED. INVOICE #3171.

Plugged through: CSG

District: 02

Signed Michael P Wilson
(TECHNICIAN)

INVOICED

DATE Feb 8-02

2002061363