

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-21180-00-00
Spot: N2SWNE Sec/Twnshp/Rge: 15-20S-3W
3630 feet from S Section Line, 1980 feet from E Section Line
Lease/Unit Name: STUCKY B Well Number: 2
County: MCPHERSON Total Vertical Depth: 3135 feet

Operator License No.: 6159
Op Name: SIEMENS, HANK DBA S & H OILFIELD E
Address: PO BOX 168
MOUND RIDGE, KS 67107

Conductor Pipe: Size feet: \$101.89
Surface Casing: Size 8.625 feet: 214 135 SX CMT
Production: Size 5.5 feet: 3134 100 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/23/2002 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: HANK SIEMENS Company: KANK SIEMENS DBA/S & H OILFIE Phone: (620) 345-8405

Proposed Plugging Method: Sand to 3,020' and top with 5 sxs. cement. Shoot pipe off. Pull pipe to 525' and spot 35 sxs. cement. Pull pipe to 300' and circulate cement to the surface.

Plugging Proposal Received By: MICHAEL WILSON
Date/Time Plugging Completed: 01/23/2002 1:00 PM

Witness Type: Plugging Operations Partially Witnessed
KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Sanded to 2,981' and topped with 5 sxs. cement. Shot casing off at 1,830'. Pulled casing to 535' and spotted 35 sxs. cement. Pulled casing to 292' and circulated 110 sxs. cement to the surface. Topped off with 50 sxs. cement on 01/24/02.

RECEIVED
KCC DISTRICT #2

FEB 07 2002

WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY UNITED. INVOICE #3173.

Plugged through: CSG

District: 02

Signed Michael Wilson
(TECHNICIAN)

INVOICED

DATE Feb 8-02

INV. NO. 2002061363