

15.113.20945.0000
2-010197

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

6-11

API NUMBER: 15-113-20-834

NE-NE-SE SECTION 14 TOWNSHIP 20S RANGE 3W

OPERATOR LICENSE # 30009 2,279' FEET FROM S SECTION LINE
OPERATOR Randon Production Co. 279' FEET FROM E SECTION LINE
NAME & 2761 N. Remington Road
ADDRESS Marion, KS 66861
LEASE NAME: Junke #1
COUNTY McPherson
WELL TOTAL DEPTH: 3,063' 99.55
PIPE: _____
SURFACE CASING 8 5/8" at 201'

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SWD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Larry George Sage

ADDRESS: P.O. Box 12 Virgil, KS 66870 LICENSE: #5684

COMPANY TO PLUG AT: HOUR: 12:00 DAY: 9 MONTH: 6 YR: 1999

PLUGGING PROPOSAL RECEIVED FROM: George Sage

COMPANY NAME: Larry George Sage PHONE: 316-678-3440

WERE: Sand to 3010' and top with 4 sxs. cement. Shoot pipe off. Pull pipe to 500' and spot 35 sxs. cement. Pull pipe to 275' and circulate cement to the surface.

4 1/2" casing at 3,063'.

Perforations from 3,048' to 3,052'.

PLUGGING PROPOSAL RECEIVED BY: Michael R. Wilson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 11:00 DAY: 11 MONTH: 6 YEAR: 1999

ACTUAL PLUGGING REPORT: Sanded to 3,000' and topped with 4 sxs. cement. Shot pipe off at 1,495' and pulled same. Ran 2 3/8" tubing to 510' and spotted 35 sxs. cement. Pulled tubing to 270' and circulated 92 sxs. cement to the surface.

Retrieved 1,495' of 4 1/2" casing (37 jts.).

REMARKS: Used 60/40 posmix by George Sage. Invoice # 1R. Used United pump truck for spotting of plugs. Invoice #5578.

I DID OBSERVE THIS PLUGGING.

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 25 1999
CONSERVATION DIVISION
WICHITA, KS

Michael R. Wilson
Michael R. Wilson

INVOICED
DATE 6-28-99
INV. NO. 61097

FORM CP-2/3
REV. 3/90

De