

1 050877

JAN 3 1 1987

15-097 - 20850-8000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-N/A

C NE SW, SEC. 25, T 28 S, R 19 W/E

1980 feet from S section line

3300 feet from E section line

Lease Name Heinze Well # 1-25

County Kiowa

Well Total Depth 4999 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 325

TECHNICIAN'S PLUGGING REPORT

Operator License # 9123

Operator: Diamond Shamrock Exploration Comp.
Name & Address: for Commonwealth Petroleum
P.O. Box 400
Amarillo, TX 79188-0001

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address Box 506, Liberal, KS 67901

Company to plug at: Hour: 9 a.m. Day: 31 Month: 1 Year: 19 87

Plugging proposal received from Don Bagley

(company name) Diamond Shamrock Exploration Company (phone) 806-378-4154

were: 4 1/2" at 4999' Perfs at 4906-16'

1st plug pump 1 sx hulls and 25 sx cement and stop plug at 4800',

2nd plug at 1200' with 50 sx cement,

3rd plug at 360' with 50 sx cement,

4th plug at 40-0' with 10 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 3 p.m. Day: 31 Month: 1 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 25 sx cement and stopped plug at 4800',

2nd plug at 1200' with 50 sx cement,

3rd plug at 360' with 50 sx cement,

4th plug at 40' with 10 sx cement.

Remarks: Recovered 2502' of 4 1/2" casing. Used common cement by Sargent's.

(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 2-3-87

INV. NO. 16067

1-31

STATE CORPORATION COMMISSION

2-3-87

Signed Richard W. Lacy
(TECHNICIAN)