

1 010137

Docket No. E-15,010 15-007-013950-01

Completed 8-20-51

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-

NW SE SE, SEC. 17, T 33 S, R 12 W/XX

990 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5357

Lease Name Boggs "C" Well # 14

Operator: Frank J. Black

County Barber 160.23

Name & Address P. O. Box 250

Well Total Depth 4930 feet

McPherson, KS 67460

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 600

Abandoned Oil Well Gas Well Input Well SWD Well ~~X~~ D&A

Other well as hereinafter indicated

Plugging Contractor Nicholas Casing Pulling License Number 6698

Address P. O. Box 206, Geneseo, KS 67444

Company to plug at: Hour: 1:50 pm Day: 13 Month: May Year: 19 86

Plugging proposal received from Allen Nicholas

(company name) Nicholas (phone) 316-824-6467

were: 5 1/2" at 4875' Squeezed at 950'

Squeeze 5 1/2" with 1 sack hulls, 25 sx over perfectfill of econolite

Pump 100 sx cement down 8 5/8" x 5 1/2" annulus with econolite

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2:20 pm Day: 13 Month: May Year: 19 86

ACTUAL PLUGGING REPORT Squeezed well with 3 sx hulls, 30 sx cement, 25 sx gel and 65 sx cement.

Pumped 100 sx cement down annulus.

5-16-86 - ran 210' of 1" on backside and circulated to surface - 35 sx. The cement had fallen in the 5 1/2" and took 120 sx to fill to surface.

Maximum pressure 150 psi and shut in 50 psi

Remarks: No recovery. Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED

DATE MAY 27 1986

Signed Jack R. [Signature] (TECHNICIAN)

INV. NO. 13971

STATE CORPORATION COMMISSION  
MAY 27 1986  
CONSERVATION DIVISION  
Wichita, Kansas