

To: 1 060720
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-097-21,187-0000
C-SENE SEC. 13, T. 28 S, R. 20 W
3300 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7105 Lease Name Palatin Well # 1-13
Operator: Spines Exploration, Inc. County Keosauqua 162.50
Name & Address 530-4th Financial Ctr.
Wichita, Kansas
67202 Well Total Depth 5000 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 4 1/8 feet 605

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated anhydrite base @ 1257 Cor. 2292 ft.

Plugging Contractor Eagle Drilling Co License Number 5380

Address Wichita Kansas 67208

Company to plug at: Hour: 5:00AM Day: 12 Month: October Year: 19 85

Plugging proposal received from Butch Steinent

(company name) Eagle Drilling Co (phone) 316-672-6639

were: 1st plug @ base of the anhydrite w/ 50 sbx cement.

2nd plug @ 1/2 anhydrite w/ 50 sbx cement

3rd plug 30' out of surface w/ 50 sbx cement.

4th plug @ 40' on solid bridge wood plug w/ 10 sbx cement filling hole to 0'

5th plug circulate 10 sbx cement in rat hole & 10 sbx cement in mouse

hole use 60/40 pass w/ 6% gel Plugging Proposal Received by Paul A. Luthin
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 8:30AM Day: 12 Month: October Year: 19 85

ACTUAL PLUGGING REPORT 1st plug @ 1260' w/ 50 sbx cement.

2nd plug @ 930' w/ 50 sbx cement.

3rd plug @ 630' w/ 50 sbx cement.

4th plug @ 40' on solid bridge wood plug w/ 10 sbx cement filling hole to 0'

5th plug circulated 10 sbx cement in rat hole & 10 sbx cement in mouse

hole. R.J. Titan pumped 60/40 pass w/ 6% gel through

drill pipe w/ hole full of heavy mud.
(If additional description is necessary, use BACK of this form.)

INVOICED RECEIVED
STATE CORPORATION COMMISSION

DATE NOV 22 1985

NOV 18 1985

Signed Paul A. Luthin
(TECHNICIAN)

INV. NO. 11159

CONSERVATION DIVISION
Wichita, Kansas