

15-097-20530-0001
K

1060667

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- N/A
C SE SE, SEC. 32, T 28 S, R 20 W/R
660 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5414
Operator: J. Mark Richardson
Name & Address: 640 Century Plaza,
Wichita, KS 67202

Lease Name Steve Brown Well # 1
County Kiowa 165.75
Well Total Depth 5100 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 605

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893
Address P. O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 1:30 pm Day: 24 Month: September Year: 19 85

Plugging proposal received from Carl Shields

(company name) J. Mark Richardson (phone) 316-262-3192

were: 4 1/2" at 5099' Perfs at 4448-53'

1st plug sand back to 4395' and dump 4 sx cement on top of sand through bailer
2nd plug squeeze well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,
release 8 5/8" rubber plug and pump 125 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:10 pm Day: 24 Month: September Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4395' and dumped 4 sx cement on top of
sand through bailer, 2nd plug squeezed well with 2 sx hulls, 10 sx gel, 50 sx cement,
10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 125 sx cement.

Maximum pressure 500 psi and shut in 250 psi

Remarks: Recovered 2703' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED
STATE CORPORATION COMMISSION

Signed Paul A. Luthi (TECHNICIAN)

DATE 10-10-85

OCT 4 1985
10-4-85

INV. NO. 10412

9-24 OCT 23 1985 CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84