

JUN 2 3 1987

API NUMBER 15- 097-21,241-0000

To: 1 050917
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C SW SE, SEC. 34, T 28 S, R 20 W/E
660 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5414

Lease Name Sherer A Well # 2

Operator: J. Mark Richardson
Name & Address 640 Century Plaza Bldg.
Wichita, KS 67202

County Kiowa 164.35
Well Total Depth 5057 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 619

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Gabbert-Jones, Inc. License Number 5842

Address English Key Bldg, 333 East English, Suite 215, Wichita, KS 67202

Company to plug at: Hour: 1 p.m. Day: 23 Month: 6 Year: 1987

Plugging proposal received from Carl Shield

(company name) J. Mark Richardson (phone) 316-262-3192

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2320'
Anhydrite 1230'

1st plug at 1260' with 50 sx cement,

2nd plug at 630' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 3:30 p.m. Day: 23 Month: 6 Year: 1987

ACTUAL PLUGGING REPORT 1st plug at 1260' with 50 sx cement,

2nd plug at 630' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

6-30-87

RECEIVED
STATE CORPORATION COMMISSION

JUN 30 1987

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-1-87

INV. NO. 17406

6-23

JUL 3 0 1987

Signed Richard W. Lacey
(TECHNICIAN)

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date JUNE 12, 1987 month day year

API Number 15-097-21,241

OPERATOR: License # 5414 Name J. Mark Richardson Address 640 Century Plaza Bldg Wichita, Kansas 67202 Contact Person J. Mark Richardson Phone (316) 262-3192

C SW SE Sec 34 Twp 28 S, Rg 20 West 660 Ft. from South Line of Section 1980 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 660 feet County Kiowa

CONTRACTOR: License # 5842 Name Gabbart-Jones, Inc City/State Wichita, Kansas

Lease Name Sherer A Well # 2 Ground surface elevation 2320 feet MSI

Well Drilled For: Oil SWD Infield Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl Wildcat Cable

Domestic well within 550 feet yes no Municipal well within one mile: yes no

Depth to bottom of fresh water 190 Depth to bottom of usable water 250

Surface pipe by Alternate: 2 Surface pipe planned to be set 600

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

Conductor pipe required Projected Total Depth 5100 feet

Formation Mississippi

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date Signature of Operator or Agent J. Mark Richardson Title Operator

For KCC Use: Conductor Pipe Required 270 feet; Minimum Surface Pipe Required 270 feet per Alt. This Authorization Expires 12-8-87 Approved By 6-8-87

Spud 6-17-87 - Set 600 +

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with 4 columns: Plug number, Depth (ft), Plug length (ft), and Material (Cement). Includes entries for 1st through 5th plugs and Rathole/Mousehole.

PUSHER Carl Shield by JMR

TD 5057 FORMATION Mass SURFACE PIPE 8 5/8 @ 619

ANHYDRITE 1230 ELEVATION 2320 6-23-87 STARTING TIME & DATE 1:00 PM COMPLETION TIME & DATE 3:30 PM

1st PLUG @ 1260 FT. W/ 50 SX 2nd PLUG @ 630 FT. W/ 50 SX 3rd PLUG @ 40 FT. W/ 10 SX 4th PLUG @ FT. W/ SX RAT HOLE CIRCULATED W/ 15 SX MOUSE HOLE CIRCULATED W/ SX WATER WELL PLUGGED W/ SX

CEMENT COMPANY Hall, Burton

TECHNICIAN Lacey gace orders 60/40-6%gel

RECEIVED STATE CORPORATION COMMISSION JUN 30 1987 CONSERVATION DIVISION Wichita, Kansas

Plug Noon 6-23-87