

15.159.21628.0000

2-070672

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

1-14

API NUMBER: 15-159-22,112 ^{21,628}

C.4/2 SW, SECTION 23 TOWNSHIP 20 RANGE 6W

OPERATOR LICENSE # 31534 1320 FEET FROM S SECTION LINE

OPERATOR SUSAN SWANSON 4950 FEET FROM E SECTION LINE

NAME & 972 PLUM AVENUE

ADDRESS WINDOM, KS 67491

LEASE NAME: HUBENETT #1

COUNTY: RICE 122.10

WELL TOTAL DEPTH: 3757'

PIPE: 5 1/2" @ 3756'

SURFACE CASING: 8 5/8" @ 259'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: QUALITY WELL SERVICE

ADDRESS: 249 EAST BETH DRIVE, STERLING, KS 67379 LICENSE: 31925

COMPANY TO PLUG AT: HOUR: 12:00 DAY: 14 MONTH: 1 YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: RICHARD

COMPANY NAME: QUALITY WELL SERVICE PHONE: (316) 727-3410

WERE: SAND TO 3260' - 5 SACKS

35 SACKS AT 850'

300'-0'

PLUGGING PROPOSAL RECEIVED BY: MICHAEL R. WILSON

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL PART NONE

COMPLETED: HOUR: 3:00 DAY: 14 MONTH: 1 YEAR: 1997

ACTUAL PLUGGING REPORT: SANDED BOTTOM TO 3260' - 5 SACKS OF COMMON. SHOT 5 1/2" CASING OFF AT 2575'. PULLED TO 850, PUMPED 200# HULLS, 35 SACKS OF CEMENT. PULLED TO 310'. CIRCULATED CEMENT TO SURFACE. TOPPED WITH 40 SACKS.

REMARKS: 60/40 POZ 4% GEL UNITED #4876

RECEIVED
KANSAS CORPORATION COMMISSION
INVOICED
DATE JAN 29 1997 JAN 29 1997 1-29-1997
INV. NO. 49487
CONSERVATION DIVISION
WICHITA, KS
1-14
MAR 14 1997

I DID OBSERVE THIS PLUGGING.
Jack Luthi
JACK LUTHI
FORM CP-2/3
REV. 3/90