


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD

Kiowa County. Sec. 17 Twp. 28S Rge. (E) 20W(W)

Location as "NE/CNW%SW%" or footage from lines C NW SE  
Lease Owner Okmar Oil Company  
Lease Name Shumway Well No. 1  
Office Address 125 N. Market, Suite 1130, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 10-22 19 73  
Application for plugging filed 10-22 19 73  
Application for plugging approved 10-22 19 73  
Plugging commenced 10-22 19 73  
Plugging completed 10-22 19 73  
Reason for abandonment of well or producing formation No commercial quantities of oil or gas encountered.  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 5000 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Hole	Fluid	Surface	533	8-5/8"	525	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Fluid to 450', plug, 40 sx cement;  
Fluid to 40', plug, 15 sx cement;  
Two sx cement in rat hole.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 2 1973  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor D N B DRILLING, INC.  
Address 701 First National Bank Bldg., Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF \_\_\_\_\_, SS.  
JAMES L. DONELSON (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James L. Donelson  
701 First Nat'l Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 31st day of October 19 73

My commission expires August 25, 1976

Ella Priess

Notary Public.

Ella Priess  
STATE NOTARY PUBLIC  
Sedgwick County, Kansas  
My Com. Expires Aug. 25, 1976

DRILLERS' LOG

OKMAR OIL COMPANY  
No. 1 Shumway  
C NW SE, Sec. 17-28S-20W  
Kiowa County, Kansas

Elevation: 2328 K.B.

Commenced: 10-15-73  
Completed: 10-22-73

Surface Casing: 524.50' of  
8-5/8" cemented w/300 sx  
Halliburton Lite cement and  
100 sx 60-40 Posmix, 3% cc.  
10-16-73

<u>FORMATION</u>	<u>DEPTH</u>
Surface Hole	0 - 533
Shale & Sand	533 - 875
Shale	875 - 1282
Anhydrite	1282 - 1309
Shale	1309 - 2125
Shale & Lime	2125 - 2265
Lime & Shale	2265 - 3755
Lime	3755 - 3985
Lime & Shale	3985 - 4435
Lime	4435 - 5000 T.D.

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

*James L. Donelson*  
JAMES L. DONELSON

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 2 1973  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS: ss:

Subscribed and sworn to before me, the undersigned, a Notary Public in and for said state, this 31st day of October, 1973.

My Commission Expires:  
August 25, 1976

*Ella Priess*  
Ella Priess, Notary Public

*Ella Priess*  
STATE NOTARY PUBLIC  
Sedgwick County, Kansas  
My Com. Expires Aug. 25, 1976