

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY KIOWA SEC. 26 TWP. 28S RGE. 20W E/W  
Location as in quarters or footage from lines:  
C SW NE


Lease Owner W.L. KIRKMAN, INC.  
Lease Name HAYSE Well No. #1  
Office Address P.O. BOX 18611, WICHITA, KS. 67207  
Character of Well (Completed as Oil, Gas or Dry Hole): DRY HOLE  
Date Well Completed 6-30-83  
Application for plugging filed July 14, 1983  
Plugging commenced 6-22-83, 7:45 P.M.  
Plugging completed 6-30-83, 5:15 P.M.  
Reason for abandonment of well or producing formation \_\_\_\_\_

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Richard Lacey

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
	8 5/8"	0	289'	J-55	7 Jts.	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Well was plugged accordingly: Total 165 sks, 60/40 pos cement, 2% gel, 3% cc., 50 sks at 1290', 40 sks at 660', 40 sks at 300', Push 1 - 8 5/8" plug to 40'. Cement 10 sks to surface, cement 15 sks in rathole, 10 sks mousehole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Cementing, Great Bend, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ross Harris ROSS HARRIS  
CORP. CONTROLLER  
Box 18611, Wichita, Ks. 67207  
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of July, 19 83

Kathleen G. Quinn  
Kathleen G. Quinn Notary Public  
STATE CORPORATION COMMISSION

My Commission expires: March 20, 1987



JUL 15 1983

CONSERVATION DIVISION  
Wichita, Kansas

ALDEBARAN

453 SOUTH WEBB ROAD  
P.O. BOX 18611  
WICHITA, KANSAS 67207  
(316) 685-5372

15-097-20954-0000



W E L L L O G

WELL NAME: HAYSE #1

WELL LOCATION: C SW NE

SEC. 26-28S-20W

OPERATOR: W.L. KIRKMAN, INC.

COMMENCED: 6-22-83 7:45 P.M.

CONTRACTOR: ALDEBARAN DRILLING CO., INC.

COMPLETED: 6-30-83 5:15 P.M.

CASING RECORD: \_\_\_\_\_

8 5/8" set @ 289'

FORMATION:

FROM:

TO:

Red Bed and Sand  
Red Bed  
Lime and Shale

0  
300'  
2220'

300'  
2220'  
5052

RECEIVED  
STATE CORPORATION COMMISSION

JUL 15 1983

CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS )  
COUNTY OF SEDGWICK) SS:

I CERTIFY THAT THIS IS A TRUE AND CORRECT COPY OF THE DRILLER'S LOG ON THE WELL DRILLED  
C SW NE, SEC. 26-28S-20W, KIOWA COUNTY TO THE BEST OF MY  
KNOWLEDGE AND BELIEF.

ALDEBARAN DRILLING CO., INC.  
*Ross Harris* ROSS HARRIS  
CORP. CONTROLLER

SUBSCRIBED AND SWORN TO BEFORE ME THIS 14TH DAY OF JULY, 1983

MARCH 20, 1987

*Kathleen G. Quinn*  
KATHLEEN G. QUINN  
NOTARY PUBLIC

