


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Flat

RICE County. Sec. 25 Twp. 20S Rge. (E) 6 (W)
Location as "NE/CNW/SW" or footage from lines NE-SW-SE
Lease Owner PLAINS EXPLORATION COMPANY
Lease Name HANSON Well No. 2
Office Address DENVER, COLORADO
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 1-20-55 19
Application for plugging filed 2-22-57 19
Application for plugging approved 2-23-57 19
Plugging commenced 5-5-57 19
Plugging completed 5-8-57 19
Reason for abandonment of well or producing formation Exhausted

If a producing well is abandoned, date of last production 2-20-57 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. RUEL DURKEE
Producing formation Miss. Chat Depth to top Bottom Total Depth of Well 3578 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	120'	None
				5 1/2"	3326'	2820'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Original plug back, cement dumped with bailer 3379' To 3350'
Sand from 3350' To 3320'
Six sacks of cement dumped with bailer
Mudded hole to 160'
Made rock bridge
Mixed and dumped 25 sacks of cement
mudded hole to 15' below bottom of cellar
Mixed and dumped 5 sacks of cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor STERLING DRILLING CO.
Address STERLING, KANSAS

STATE OF KANSAS, COUNTY OF RENO, ss.
E. E. Duncan (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *E. E. Duncan*
By: E. E. Duncan Prod. Supt.
Hutchinson Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 9th day of March 1957, 19


My commission expires 29 July, 1957

Hanson
RECEIVED
STATE CORPORATION COMMISSION
Notary Public.

PLUGGING
FILE SEC 23 T. 20 R. 6W
BOOK PAGE 142 LINE 39

MAR 11 1957
CONSERVATION DIVISION
Wichita, Kansas

3-11-1957



WELL LOG

Location NE SW SE Section 23-20S-6W,
Rice County, Kansas

OWNER: Plains Exploration Company, Sterling Drilling Company
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company
CABLE TOOL CONTRACTOR: Sterling Drilling Company

COMMENCED: 12-31-54 (w.r.)
 1-13-55 (w.c.t.)
COMPLETED: 1-10-55 (w.r.)
 1-21-55 (w.c.t.)

ROTARY TOTAL DEPTH: 3327'

LOG

0-120	Clay & Shale
120-140	Red Bed & Shale
140-800	Shale
800-1210	Limestone
1210-1850	Limestone & Shale
1850-2230	Shale
2230-3150	Limestone
3150-3285	Limestone & Shale
3285-3322	Shale
3322-3327	Chert T.D.

CASING RECORD

Ran 120' of 8-5/8" casing set with
100 sacks cement.

Ran 3330' of 5-1/2" casing set at
3327' with 50 sacks cement.

CABLE TOOLS M.I.C.T. Swabbed mud and drilled cement. Drilled new hole to 3378'.
Hole filled with 80 gal. oil and 90 gal. of water in 8 hours. Sand fractured with
20,000# sand and 175 bbls. heavy crude oil at 1100 psi to 500 psi. Swabbed back load
oil and swabbed at rate of 13 bbls. fluid per hour estimated 25% oil with 100 bbls. load
oil remaining. M.O.C.T. P.O.P.

PLUGGING			
FILE	SEC. 23	T. 20	R. 6W
BOOK	PAGE 142	LINE	39

RECEIVED
STATE CORPORATION COMMISSION

FEB 23 1957

CONSERVATION DIVISION
Wichita, Kansas