


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Rice County. Sec. 23 Twp. 20S Rge. 6W (E) (W)
Location as "NE/CNW*SW*" or footage from lines NW NE
Lease Owner Plains Exploration Co.
Lease Name Fry "I" Well No. 1
Office Address Denver, Colo.
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed June 20 1969
Application for plugging filed February 12, 1969
Application for plugging approved February 13 1969
Plugging commenced Feb. 17 1969
Plugging completed Feb. 20 19 1969
Reason for abandonment of well or producing formation Depletion

If a producing well is abandoned, date of last production February 1969
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3324 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled back with sand to 3250'. Dumped 5 sacks of cement. Shot pipe off at 2962.70'. Pulled pipe and mudded hole to 210'. Set rock bridge from 210' to 200' and dumped 25 sacks of cement. Finished mudding hole and dumped 10 sacks of cement at base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
FEB 25 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Bert Self
Address Hutchinson, Kans.

STATE OF Kans., COUNTY OF Reno, ss.
Employee (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bert Self

R. R. #4, Hutchinson, Kans.

Subscribed and sworn to before me this 20th day of February, 1969



My commission expires October 18, 1969

Notary Public.

STERLING DRILLING COMPANY
Sterling, Kansas

WELL LOG ----- FRY "I" #1
LOCATED: C NW NE Section 23-20S-6W, Rice County, Kansas

OWNER: Plains Exploration Company
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: June 5, 1966
COMPLETED: June 12, 1966

ROTARY TOTAL DEPTH: 3306'

LOG		CASING RECORD
0 - 755	Shale & Lime	Ran 4 joints (154') 8-5/8", pipe set at 166' K.B., cemented with 170 sacks HA-5. Plug was down at 1:30 a.m.
755 - 1090	Shale, Lime & Shells	
1090 - 1205	Lime	
1205 - 1505	Lime & Shale	
1505 - 1599	Lime	
1599 - 2500	Lime & Shale	
2500 - 2670	Sand & Shale	
2670 - 2915	Lime & Shale	
2915 - 3250	Lime	
3250 - 3306	Shale & Lime T.D.	Ran 101 joints 5-1/2" 11#, tested 4000# set at 3304.5' with 50 sacks cement. Plug down at 10:00 a.m. 6-12-66. K.B. is 10.50' above braden head.

FORMATIONS: Brown Lime 2703' (-1135') Lansing K.C. 2724' (-1156')
Mississippian 3295' (-1727')

CABLE TOOL RECORD: Drilled new hole to 3324' or 18'. Forty-hour fillup showed 51 gallons of fluid, about 20% live oil. Moved cable tools off. Will frac and test further with pumping unit. Cable Tools completed June 20, 1966.