

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

*Pl*  
WELL PLUGGING RECORD

Rice County. Sec. 26 Twp. 20s Rge. 6w (E) (W)

Location as "NE/CNW/SW" or footage from lines G NW SW

Lease Owner Plains Exploration Company

Lease Name Lindholm Well No. # 1

Office Address 3600 North Halsead Hutchinson, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_

Date well completed \_\_\_\_\_ 19\_\_

Application for plugging filed yes 19\_\_

Application for plugging approved yes 19\_\_

Plugging commenced 7-28-60 19\_\_

Plugging completed 8-2-60 19\_\_

Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3381' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		3,114'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugging commenced 7-28-60. Plugging completed 8-2-60. Measured into total depth, 3381'. Plugged off bottom. Sanded back up hole to 3350' and dumped 5 sacks of cement. Worked and shot pipe. Shot 5 1/2" casing free at 3,114'. Built rack and slide. Pulled and laid down casing. Mudded hole up to 160'. Set 10' rock bridge at 160'. Dumped 20 sacks of cement at 160'. Mudded hole up to 40' and set 10' rock bridge at 40'. Capped the well with 10 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 16 1960  
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J. O. Forbes d/b/a Forbes Casing Pulling

Address Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes  
J. O. Forbes  
Box 221 Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of August, 19 60

My commission expires December 8th, 1969

Kayann Jenkins  
Kayann Jenkins Notary Public.

STERLING DRILLING COMPANY  
Sterling, Kansas

WELL LOG ----- LINDHOLM #1

Located: C NW SW, Section 26-20S-6W, Rice Co., Kansas

OWNER: Plains Exploration Company & Sterling Drilling Company  
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: 3-5-60  
COMPLETED: 3-12-60

ROTARY TOTAL DEPTH: 3350'

LOG

0 - 163	Clay & Shale
163 - 1085	Shale, Shells & Salt
1085 - 1250	Lime
1250 - 1970	Shale & Lime
1970 - 2200	Shale
2200 - 2490	Lime
2490 - 2725	Lime & Shale
2725 - 2762	Sand & Shale
2762 - 2790	Brown Lime
2790 - 2845	K.C. Lime
2845 - 3240	Lime
3240 - 3350	Shale & Lime
3350 - 3365	Chat

CASING RECORD

Ran 8-5/8" Surface casing @  
160' with 135 sacks cement,  
2 sacks c.c.

Ran 5-1/2" casing @ 3364' with  
50 sacks cement.

**RECEIVED**  
STATE CORPORATION COMMISSION

JUL 22 1960

CONSERVATION DIVISION  
Wichita, Kansas