

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging of formations.

STATE OF KANSAS STATE CORPORATION COMMISSION

Give All Information Completely Make Required Affidavit Mail or Deliver Report to: Conservation Division State Corporation Commission 300 Bitting Building Wichita, Kansas

Rice County. Sec. 26 Twp. 20S. Rge. (E) 6 (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines NW NW NW

Lease Owner PETROLEUM, INC.

Lease Name Hubenett Well No. 1

Office Address Derby Building

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 12/30/48 19

Application for plugging filed 1/8/49 19

Application for plugging approved 12/30/48 19


Plugging commenced 12/30/48 19

Plugging completed 12/30/48 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Flat

Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation Depth to top Bottom Total Depth of Well 3410 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Row 1: Surface casing, 0, 124', 8 5/8, 12/18/48.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole was plugged per instructions of Ruel Durkee, as follows:

- Heavy rotary mud from 3410 to 117
15 sacks of cement from 117 to 72
Heavy rotary mud from 72 to 16
5 sacks of cement from 16 to 6
Rock & surface soil from 6 to top

RECEIVED stamp

Conservation Div.

JAN 11 1949

STATE CORPORATION COMMISSION KANSAS

1-11-1949

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to PETROLEUM, INC. Address Derby Building, Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick ss. Charles M. Searle

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Charles M Searle

Derby Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this day of 19

Notary Public.

My commission expires



15.159.03363.0000

COMPANY Petroleum, Inc., Wichita, Kansas  
 LEASE Hubennett Well No. 1  
 LOCATION NW/4 NW/4 NW/4, Section 26-20S-6W, Rice County, Kansas  
 CONTRACTOR J. A. Melland, Hutchinson, Kansas  
 Work Commenced Dec. 16, 1948 Drilling Commenced Dec. 17, 1948  
 Drilling Completed Dec. 30, 1948

FORMATION	FROM	TO
Surface Clay	0	15
Shells & shale	15	110
Shells & clay	110	135
Shale & shells	135	855
Anhydrite	855	875
Shale, shells & salt	875	1010
Shale and shells	1010	1200
Lime and shale	1200	1590
Shale and shells	1590	1810
Shale	1810	2270
Lime and shale	2270	2885
Lime	2885	2950
Lime	2950	3065
Lime and shale	3065	3200
Lime and shale	3200	3333
Conglomerate	3333	3340
Lime	3340	3350
Chert	3350	3365
Chert	3365	3380
Chert	3380	3391
Chert & shale	3391	3410
ROTARY TOTAL DEPTH		3410'

Set & cemented 8-5/8"OD csg. at 124' w/  
 100 sacks Halliburton Bulk Cement.  
 Finished cementing 4:00 AM, 12/18/48.

Ran Halliburton Drill Stem test at  
 3340' - Recovered 20' mud - No shows

Ran Halliburton Drill Stem test at 3365',  
 Recovered 30' mud, no shows

Finished drilling 12/30/48  
 Orders received at 8:00 AM, 12/30/48  
 to plug & abandon.

Hole plugged as per instructions of Ruel Durkee, S.C.C. plugger.

Heavy rotary mud from	3410 to	117
15 sacks cement	117 to	72
Heavy rotary mud from	72 to	16
5 sacks cement	16 to	6
Rock & surface soil	6 to	top

Plugging completed 12 noon, 12/30/48.

**RECORDED**  
 COMMISSION DIV.  
 JAN 8 - 1949  
 STATE CORPORATION  
 COMMISSION  
 KANSAS

I, J. A. Melland, do hereby certify that the above is a true and exact driller's log of the Hubennett Well No. 1

J. A. Melland 1/3/49  
 J. A. Melland, Contractor

Subscribed and sworn to before me this 30th day of December, 1948

My commission expires:

*October 27, 1952*

Marjorie Bradshaw  
 Notary Public

**PLUGGING**  
 FILE SEC 26-T-20-R (60)  
 BOOK PAGE 77 LINE 14