

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 13.159.21907.0000

LEASE NAME Lindholm

WELL NUMBER #1

SPOT LOCATION NE NE NW

SEC. 26 TWP. 20S RGE. 6W (E) or (W)

COUNTY Rice

Date Well Completed 10-4-84

Plugging Commenced 2-18-86

Plugging Completed 2-26-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Champion Petroleum, Inc.

ADDRESS P.O. Box 340 Great Bend, Kansas 67530

PHONE # (316) 792-1314 OPERATORS LICENSE NO. 9263

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Salina, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 3410'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	256'	none
				5-1/2"	3409'	2624'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged off bottom tih sand to 3250' and 5 sacks cement. Shot casing @2819', 2624',
laid down 66 joins of 5-1/2" casing. Plugged surface with 5 sks. hulls, 20 sks, gel,
8-5/8" plug, 100 sks. cement, 60/40 pos, 6% gel.
Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

(Signature) R. Darrell Kelso
(Address) P.O. Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 27th day of February, 1986

HELENE J. JONES
STATE CORPORATION COMMISSION
Notary Public

My Commission expires:



MAR 3 1986

3-3-1986

CONSERVATION DIVISION
Wichita, Kansas

Form CP-4
Revised 01-84



WELL DRILLING RECORD

OPERATOR: CHAMPION PETROLEUM, INC.
 WELL: #1 LINDHOLM
 LOCATION: NE-NE-NW SECTION, 26-20S-6W
 COUNTY: RICE COUNTY, KANSAS
 DRILLING CONTRACTOR: MUSTANG DRILLING & EXPLORATION, INC.
 ELEVATIONS: 1565' G. L. D. F. K. B.
 SURFACE CASING: 8-5/8" 256' WITH 200 SACKS
 PRODUCTION CASING: 5-1/2" @ 3409' 125 WITH SACKS
 SPUD DATE: 9-28-84
 COMPLETION DATE: 10-4-84

DAILY DRILLING REPORT

9-27-84 LOCATION STAKED AND ELEVATION SHOT
 9-28-84 DIGGING PITS
 MUSTANG DRILLING MOVING IN ON LOCATION THIS
 AFTERNOON.
 9-29-84 SURFACE SET AT 256' WITH 200 SACKS OF
 CEMENT.
 9-30-84 7:00 A. M. DRILLING AHEAD @ 1641'

 10-1-84 7:00 A. M. DRILLING AHEAD @ 2500'
 10-2-84 7:00 A. M. DRILLING AHEAD @ 3032'
 10-3-84 MISSISSIPPIAN CAME IN 8' HIGH TO THE OFFSET
 DRY HOLE. THE SHOW OF OIL WAS GOOD AND WE
 EXPECT TO SET 5 1/2" PRODUCTION CASING
 TONIGHT. RAN OPEN HOLE LOG WHICH CALCULATED
 POSITIVE. THE LOG SHOWS INCREASE IN POROSITY
 TO THE OTHER WELLS IN THE AREA.
 10-4-84 RAN 5 1/2" PRODUCTION CASING, SET AT 3409'
 WITH 200 SACKS. WILL MOVE IN COMPLETION
 TOOLS IN APPROXIMATELY 2 WEEKS.

<u>FORMATION</u>	<u>LOG TOPS</u>
HEEBNER	2535 (- 966)
TORONTO	2554 (- 985)
DOUGLAS	2563 (- 994)
BROWN LIME	2717 (-1148)
LANSING	2740 (-1171)
MISSISSIPPIAN	
"CHAT"	3312 (-1743)
MISSISSIPPIAN	
LIME	3379 (-1810)
KINDERHOOK	3401 (-1832)
R. T. D.	3410 (-1841)
L. T. D.	3411 (-1842)

JAN 29 1986
 CONSERVATION DIVISION
 State of Kansas