

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittig Building  
Wichita, Kansas

Rice County, Sec. 26 Twp. 20S Rge. 6W (E) (W)

Location as "NE/CNW%SW%" or footage from lines N/2 of SE/4

Lease Owner Stag Drilling, Inc.

Lease Name Slabach Well No. 1

Office Address Chase, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil well

Date well completed 19

Application for plugging filed January 18 19 55

Application for plugging approved January 20 19 55

Plugging commenced January 19 19 55

Plugging completed January 22 19 55

Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production Depleted 12-15 19 54

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation Depth to top Bottom Total Depth of Well 3358 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	128'	None
				5-1/2"	3320'	2991'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with sand from 3358' to 3310' and ran 6 sacks of cement. Mudded hole to 125', set a 10' rock bridge and ran 15 sacks of cement. Mudded hole to top and ran 5 sacks of cement. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Inc.

Address Chase, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Stag Drilling, Inc. by G. H. [Signature]  
(Address)

SUBSCRIBED AND SWORN TO before me this 27 day of January, 1955

My commission expires 3/1/55 [Signature] Notary Public.

PLUGGING  
FILE SEC 26 T20 R6W  
BOOK PAGE 91 LINE 38

RECEIVED  
JAN 23 1955  
CONSERVATION DIVISION  
Wichita, Kansas  
1-28-1955

## DRILLERS LOG

Company  
Contractor

Jess Cling & Etal.  
Slusser Drilling Co.

Commenced 3-17-54  
Completed 3-27-54

Farm

Slabach #1

26-20-6 Rice County, Ks.

8 5/8  
5 1/2

@ 128'  
@ 3320'

## ROTARY TOOLS

Surface Sand	5
Red Rock & Shale	128
Red Rock & Shells	320
Shale	500
Shale & Shells	790
Lime	1000
Shale & Lime	1320
Shale	1350
Lime & Shale	2035
Shale & Shells	2210
Lime & Shale	2295
Lime	2370
Lime & Shale	2455
Lime	2500
Shale & Shells	2765
Lime	2980
Shale & Lime	3045
Lime	3175
Lime & Shale	3317
Chat	3321 Rotary T. D.

Corrected back with cable tools.

Chat Hard	3313 to 3318
Chat Soft	3318 3319
Chat Hard	3319 3338
Chat Soft	3338 3340
Chat Med Hard	3340 3358 T. D.

RECEIVED  
STATE CORPORATION COMMISSION

MAY 10 1954

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING

FILE SEC 26 T. 20 R. 6W  
BOOK PAGE 83 LINE 7

PLUGGING

FILE SEC 26 T. 20 R. 6W  
BOOK PAGE 91 LINE 38