

**Kansas Corporation Commission**  
**District Plugging Report**

API Well Number: 15-091-20860-00-00  
 Spot: NW NESWSW Sec 33 Twp 13 S Rng 23  E /  W  
1217 Feet from  N /  S Line of Section  
4490 Feet from  E /  W Line of Section  
 GPS: Lat: 38.872360 Long: 94.868780 Date: 3/19/18 9/20/17  
 Lease Name: Kauffman (City of Olathe) Well #: KAU03 3  
 County: Johnson Total Vertical Depth: 600 feet

Operator License No: 101  
 Op Name: State of Kansas String: SURF - Casing Size: 7.000 Depth: 40 Pulled: 0 Comments: EST  
 Address 1: 266 N. Main St., Ste 220 String: 11 - Casing Size: 2.000 Depth: 600 Pulled: 0 Comments: EST  
 Address 2: \_\_\_\_\_  
 City: WICHITA  
 State: KS Zip Code: 67202 - 1513

Well Type: RES - Residential Gas Well UIC Docket No.: \_\_\_\_\_ Date/Time to Plug: 11/17/17 / \_\_\_\_\_  
 Plug Co License No.: 3097 Plug Co. Name: K-W OIL WELL SERVICES, INC.  
 Proposal Rcvd from: JIM KEAY Company Name: K-W Phone: 620-431-2285

Proposed Plugging Report: Fill well with portland cement from TD to surface.

Plugging Proposal Received By: Frank Guilfoyle Witness Type: COMP - Complete 100%  
 Date/Time Plugging Completed: 11/17/17 / \_\_\_\_\_ KCC Agent: Frank Guilfoyle

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
Pump water down 2" casing to kill gas to perforate well. Perforate well. Run 1" to 600 ft and hit. Pump Portland cement to surface. Pull pipe and top off well. Squeeze well with cement and pressure up to 300 PSI. Shut in well with valve. Pump total of 25 sacks of cement. Well plugged.		<u>150</u>	<u>300</u>	<u>CSG - Casing</u>

Remarks: Well plugged for City of Olathe. GPD'ed by FG NAD 83. Irreg section.

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue:  Yes  No

District: 03 KCC WICHITA Frank Guilfoyle  
 APR 05 2018 (Technician)  
 RECEIVED Form: District Plugging Report - \_\_\_\_\_