

4-060996

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

11-12

API Number: 15-009-23,948-0000

SW SW NW /4 SEC. 19, 20 S, 14 W
2970 feet from S section line
4950 feet from E section line

Operator license# 30601

Lease Clark Well # 1-19

Operator: Northstar Investments, Inc.

County: Barton 122.20

Address: 13735 Pinnacle
Wichita, Kansas 67230-1545

Well total depth 3760 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 883 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Quality Well Service License# 31925

Address: 249 Beth Drive - Sterling, Kansas 67579

Company to plug at: Hour: A.M. Day: 12 Month: November Year: 1996

Plugging proposal received from: Richard McIntyre

Company: Quality Well Service Phone: 316-278-2476

Were: Order 260 sxs 60/40 posmix - 10% gel and hulls.
Plug while pulling casing.

RECEIVED
STATE CORPORATION COMMISSION
DEC 12 1996
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour: P.M. Day: 12, Month: November Year: 1996

Actual plugging report: 8 5/8" to 883' w/275 sxs. 5 1/2" to 3751' w/150 sxs. Perfs at 3625' - 3629' and 3633' - 3639'. Hit bridge at 880'. Pushed down to 3317'. Sanded to 3209' and spotted 5 sxs cement with dumpb bailer. Shot casing loose at 1940' and pulled to 1625'. Mixed and pumped 115 sxs cement wit 300# hulls. Pulled casing to 925' and pumped 40 sxs. Pulled casing to 440' and circulated cement with 90 sxs. Pulled casing and topped with 15 sxs.

Remarks: Allied Cementing - Ticket # 4451

Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO

Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO

Plugged through TUBING, CASING X. Elevation: 1910 GL

I did [] / did not [X] observe the plugging.

INVOICED

DATE DEC 03 1996

INV. NO. 47080

1-28-97

[Signature]
DK (agent)

Form CP-2/3

11-12 JAN 28 1997