

6 061934

API NUMBER 15-

009-22,903.0000

293
R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW, SEC. 1, T 20 S, R 13 W/EX
4950 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6072

Lease Name Weller Well # 1

Operator: Rosenberg Engine Service

County Barton 114.73

Name & Address Box 253

Well Total Depth 3530 feet

Great Bend, Ks. 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 683

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers License Number 4635

Address Box 768 Great Bend, Ks. 67530

Company to plug at: Hour: 2:00 PM Day: 15 Month: August Year: 19 89

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers (phone) 316-793-9711

were: Order 200 sks 60/40 poz 8% gel 5 sks hulls.

Plugging Proposal Received by Gilbert G. Scheck
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:30PM Day: 15 Month: August Year: 19 89

ACTUAL PLUGGING REPORT 8 5/8" set at 683' w/300 sks. 5 1/2" set at 3529' w/150 sks.

Top perf at 3468'. Plugged bottom w/sand and 5 sks cement to 3400'. Shot pipe one time and recovered 2420'. Pumped in 8 5/8" 25 sks cement followed w/5 sks hulls in 175 sks cement w/400 pst.

RECEIVED
STATE CORPORATION COMMISSION

SEP - 6 1989 9-6-89

Remarks: By B. J. Titan Ran line to 1000'. CONSERVATION DIVISION
(If additional description is necessary, use BACK of this form.) Wichita, Kansas

INVOICED
DATE 9-11-89
INV. NO. 25878
observe this plugging.

Signed Gilbert G. Scheck
(TECHNICIAN)
Gilbert Scheck