

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-191-21670-00-00
Spot: NWSWNE Sec/Twnshp/Rge: 20-33S-2E
3730 feet from S Section Line, 2316 feet from E Section Line
Lease Name: HOWER Well #: 3
County: SUMNER Total Vertical Depth: 3597 feet

Operator License No.: 100
Op Name: KANSAS CORPORATION COMMISSION
Address: 266 N MAIN, SUITE 220
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3596		150 SX
SURF	8.625	268		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/12/2018 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD Company: _____ Phone: (620) 441-7223

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/12/2018 11:40 AM KCC Agent: JEFF KLOCK

Actual Plugging Report:

2/1/18 MIRU, DUG CELLAR. FLUID @ SURFACE WITH SLIGHT FLOW OVER THE CASING. FEW GAS BUBBLES BREAKING SURFACE. RAN IN WITH BAILER AND STACKED OUT ON BRIDGE @ 30'. 2/8/18 RIGGED UP POWER SWIVEL AND DRILLED DOWN TO 2620'. DRILLING SOLID @ 2,620', HITTING STEEL. PUMPED 50 SX COMMON, 100# HULLS, 4% CC. 2/12/18 COULD NOT GET PERF GUN DOWN CASING, SO 10 JOINTS OF TUBING RAN TO 300', RAN RTG GUN DOWN AND PERFORATED AT 320'. PUMPED 65 SX COMMON, TIED ONTO 4 1/2" CASING AND PUMPED 70 SX COMMON. GOOD CEMENT CIRCULATED TO SURFACE. CEMENT STAYED AT SURFACE. ***PER DOCKET NO. 17-CONS-3127-CSHO. JAED PRODUCTION CO. WAS FOUND TO BE LEGALLY RESPONSIBLE FOR THE HOWER #1 & #3, BUT ALSO ORDERED THE KCC TO PLUG THE WELLS TO PREVENT FURTHER POLLUTION.

Perfs:

Remarks: QUALITY WELL SERVICE TICKET #6799

Plugged through: TBG

District: 02

Signed Jeff Klock
(TECHNICIAN)

KCC WICHITA
APR 11 2018
RECEIVED