

5020397

2-8-88

139R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-159.60003.0002

NW NW SW, SEC. 32, T 20 S, R 9 W/EX

2310 feet from N/S section line

4950 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3648

Lease Name Shuyler Well # 1

Operator: O.C.S., Inc.

County Rice 110.34

Name & Address 2704 B. Nottingham

Well Total Depth 3395 feet

Hutchinson, KS 67502

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 202

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Nicholas Casing Pulling License Number 6698

Address Box 108, Geneseo, KS

Company to plug at: Hour: 9:00am Day: 8 Month: 2 Year: 19 88

Plugging proposal received from Allan Nicholas

(company name) Nicholas Casing Pulling (phone) _____

were: Fill hole with sand to 2820' and cement with 5 sxs cement. Squeeze hole with 5 sxs hulls, 20 sxs gentonite, 8 5/8" plug and 100 sxs 60/40 pozmix w/6% gel. Pump into 8 5/8" surface casing.

Plugging Proposal Received by Gilbert J. Tomans (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:15am Day: 8 Month: 2 Year: 19 88

ACTUAL PLUGGING REPORT Hole filled with sand to 2820' and cemented with 5 sxs. Hole squeezed with 5 sxs hulls, 20 sxs bentonite, 8 5/8" plug and 100 sxs 60/40 pozmix w/6% gel pumped into 8 5/8" surface casing.

5 1/2" @3359 w/100sxs Perfs @2872-72 1600' of 5 1/2" recovered

Remarks: Max 500# Shut-in 200# Allied #1703 (If additional description is necessary, use BACK of this form.)

INVOICED

(If additional description is necessary, use BACK of this form.)

DATE 2-29-88

FEB 23 1988

Signed Gilbert J. Tomans plp (TECHNICIAN)

INV. NO. 199390

CONSERVATION DIVISION 2-23-88