

1060885

Never permitted or used.

17R

API NUMBER 15-145-20,478-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NW, SEC. 2, T 20 S, R 16 W/K  
4770 feet from S section line  
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6050

Lease Name Hanson Well # 1 SWD  
County Pawnee 121.88

Operator: Kelso Casing Pulling  
Name & Address: P.O. Box 347  
Chase, KS 67524

Well Total Depth 3750 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 253

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well X D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 4:30 p.m. Day: 19 Month: 9 Year: 19 86

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 5 1/2" at 3750'

1st plug sand back to 3670' and dump 5 sx cement on top of sand through bailer.

2nd plug at 1050' with 2 sx hulls and 50 sx cement.

3rd plug at 525' with 50 sx cement.

4th plug at 280' with 50 sx cement, 5th plug at 40-0' with 10 sx cement.

Plugging Proposal Received by Paul Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 9:30 p.m. Day: 19 Month: 9 Year: 19 86

ACTUAL PLUGGING REPORT Allied pumped 60/40 6% gel .

1st plug sanded back to 3670' and dumped 5 sx cement on top of sand through bailer.

2nd plug at 1050' with 50 sx cement.

3rd plug at 525' with 50 sx cement.

4th plug at 280' with 50 sx cement.

Well flowing - 5th plug pumped 150 sx of A.T.L.

Maximum pressure 300 psi and shut in at 50 psi.

Remarks: Recovered 2020' of 5 1/2" casing  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION WICHITA, KS  
(If additional description is necessary, use BACK of this form.)

RECEIVED  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION WICHITA, KS

Observe this plugging.

DATE 10-15-86

10-8-86  
OCT 8 1986

Signed Paul A. Luthi  
(TECHNICIAN)

INV. NO. 15157